SCHEDULE 'A'							
TIRUMALA TIRUPATI DEVASTHANAMS							
BILL OF QUANTITIES							
NIT No.87/SE-I/TTD/2026-27				Period : 6 months			
NAME OF WORK: "Improvements to toilets and terrace in SGS Arts College, Tirupati".							
S.No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS / Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
1	1350.00	Dismatling, clearing away and carefully stacking materials useful for re-use, terracing work in roofs or floors of pan tiled or Mangalore tiles roof without roof timbers	Dismatling, clearing away and carefully stacking materials useful for re-us	Dismatling, clearing away and carefully stacking m	NA	24.90	1Sqm	33615.00
2	50.00	Demolishing and disposal of unserviceable materials within 100 metres lead. of Unreinforced cement concrete up to 15cm thickness	Demolishing and disposal of unserviceable materials within 100 metres lead.	Demolishing and disposal of unserviceable material	NA	2221.57	1Cum	111080.72
3	20.00	Demolition including stacking of serviceable materials and disposal of unserviceable materials within 100 metres lead of Brick work	Demolition including stacking of serviceable materials and disposal of unse	Demolition including stacking of serviceable mater	NA	372.39	1Cum	7448.73
4	130.00	Conveyance of waste materials such as debris, dismantling materials etc., with a lead of up to 5 kms from work site including loading unloading etc., complete	Conveyance of waste materials such as debris, dismantling materials etc.,	Conveyance of waste materials such as debris, dism	NA	116.67	1Cum	15167.51

5	5.00	Cement Concrete (1:4:8) using 40 mm (0.54 cu.m), 20mm (0.27 cu.m) and 12 mm (0.09 cu.m) nominal size hard broken granite crushed metal from any source conforming to the relevant ISI standards for foundations etc., laid in layers of not more than 15 cm thick well compacted including curing, ,machine mixing, cost and conveyance of all materials etc., complete.	Cement Concrete (1:4:8) using 40 mm (0.54 cu.m), 20mm (0.27 cu.m) and 12 m	Cement Concrete (1:4:8) using 40 mm (0.54 cu.m),	NA	5078.34	1Cum	25391.70
6	5.00	Cement Concrete (1:2.5:5) - Grade M15 using 20mm (0.54 cum) and 12mm (0.36 cum) nominal size HBG crushed metal from any source conforming to the relevant ISI Standards for foundations etc., laid in layers of not more than 15cm thick well compacted including curing cost, machine mixing, cost and conveyance of all materials etc., complete. Note: Measurement boxes shall be used for measuring the quantities of cement, aggregate and water required for the given concrete mix.	Cement Concrete (1:2.5:5) - Grade M15 using 20mm (0.54 cum) and 12mm (0.36	Cement Concrete (1:2.5:5) - Grade M15 using 20mm (	NA	5881.23	1Cum	29406.15
7		Construction of Brick Masonry im CM (1:6) using well burnt Bricks 2nd class or ground moulded (Non-modular or traditionat size) (230 x 1 10 x 70 mm)including curing, cost and conveyance of all materials as darected during execution and complyang with stanciard specifications etc.. complete	Construction of Brick Masonry im CM (1:6) using well burnt Bricks 2nd class	Construction of Brick Masonry im CM (1:6) using we		0.00		
a	5.00	-do- in 1st floor	-do- in 1st floor	-do- in 1st floor	501 504	8042.05	1Cum	40186.15
b	5.00	-do-in 2nd floor	-do-in 2nd floor	-do-in 2nd floor	501 504	8344.82	1Cum	41699.04
c	5.00	-do- in 3rd floor	-do- in 3rd floor	-do- in 3rd floor	501 504	8647.54	1Cum	43211.78
d	5.00	-do-in 4th floor	-do-in 4th floor	-do-in 4th floor	501 504	8950.29	1Cum	44785.48

8		Construction of 110 mm thick Brick partition walls CM (1:4) using well burnt bricks 2nd class or ground moulded (Non modular or traditional size) bricks (230X110X70 mm) including curing, cost and conveyance of all materials etc,. complete	Construction of 110 mm thick Brick partition walls CM (1:4) using well bu	Construction of 110 mm thick Brick partition wall				
a	40.00	-do- in 1st floor	-do- in 1st floor	-do- in 1st floor	502 504	996.69	1Sqm	39870.18
b	40.00	-do- in 2nd floor	-do- in 2nd floor	-do- in 2nd floor	502 504	1039.73	1Sqm	41591.84
c	40.00	-do- in 3rd floor	-do- in 3rd floor	-do- in 3rd floor	502 504	1082.76	1Sqm	43313.07
9		Plastering in Cement mortar using best river sand from approved quarry including cost and conveyance of all materials, screening, curing, rounding of corners, incidental charges as directed during execution complying with standard specifications etc., complete for the following proportions	Plastering in Cement mortar using best river sand from approved quarry i	Plastering in Cement mortar using best river san				
I		-do- CM (1:5) 12mm thick	-do- CM (1:5) 12mm thick	-do- CM (1:5) 12mm thick				0.00
a	70.00	-do-in 1st floor	-do-in 1st floor	-do-in 1st floor	901 903	315.03	1Sqm	22051.77
b	70.00	-do- in 2nd floor	-do- in 2nd floor	-do- in 2nd floor	901 903	345.72	1Sqm	24200.05
c	70.00	-do- in 3rd floor	-do- in 3rd floor	-do- in 3rd floor	901 903	376.40	1Sqm	26348.34
II		-do- in CM (1:5) 20mm thick	-do- in CM (1:5) 20mm thick	-do- in CM (1:5) 20mm thick	901 903			0.00
a	70.00	-do- in 1st floor	-do- in 1st floor	-do- in 1st floor	901 903	483.41	1Sqm	33838.70
b	70.00	-do-in 2nd floor	-do-in 2nd floor	-do-in 2nd floor	901 903	529.11	1Sqm	37037.84
c	70.00	-do- in 3rd floor	-do- in 3rd floor	-do- in 3rd floor	901 903	574.81	1Sqm	40236.98
d	50.00	-do-in 4th floor	-do-in 4th floor	-do-in 4th floor	901 903	620.54	1Sqm	31026.87

10		Repair to damaged concrete (ceiling/Beams/ columns)	Repair to damaged concrete (ceiling/Beams/ columns)	Repair to damaged concrete (ceiling/Beams/ columns	NA			0.00
		The following procedure is to be adopted to repair the damaged concrete on ceiling/ Beams/ columns.	The following procedure is to be adopted to repair the damaged concrete on	The following procedure is to be adopted to repair	NA			0.00
		1) Temporary and adequate support by properly designing, staging and shuttering consisting of steel/ wooden props from the floor is to be provided. 2)(a) The damaged/ loose/ spalled/ friable concrete is to be removed by wire brushing, Scraping etc., to expose rusted reinforcement. (b) If the existing reinforcement is not damaged in terms of its size, strength,bonding properties etc., then step (4) is to be followed. (c) If the existing reinforcement (mild or tor steel) is damaged, then the same is to be replaced with new bars similar to the existing bars and then step (4) is to be followed. 3) All loose scale and corrosion deposits on the reinforcement shall be removed by Wire brushing, scraping or other mechanical means. 4) Two coats of Anti corrosive coating for steel are to be applied to avoid future rusting. 5) The exposed surface is to be finished neatly, by cement mortar duly adding suitable Polymer modifier bonding agent. 6) Curing is to be done by using a water based concrete curing compound.	1) Temporary and adequate support by properly designing, staging and shutte	1) Temporary and adequate support by properly desi	NA			0.00
		The following materials are to be used depending upon the manufacturer	The following materials are to be used depending upon the manufacturer	The following materials are to be used depending u				0.00

		MAKE: ANTI-CORROSIVE AGENT a) Dr.FIXIT DR.Fixit Rust remover b) FOSROC Nitozinc Primer Chemicals(Ind.) Pvt. Ltd. MAKE BONDING AGENT a) Dr.FIXIT DR.Fixit Micro concrete b) FOSROC Nitobond SBR Chemicals(Ind.) Pvt. Ltd. MAKE CURING COMPOUND a) Dr.FIXIT Water b) FOSROC Concure WB Chemicals(Ind.) Pvt. Ltd. NOTE: 1) The rate is excluding cost of scaffolding and plastering. 2) The rate does not include the cost of the new reinforcement replacing the existing reinforcement. If the new reinforcement is placed, the cost of the same is to be paid separately.	MAKE: ANTI-CORROSIVE AGENT a) Dr.FIXIT DR.Fixit Rust remover b) FOSROC Ni	MAKE: ANTI-CORROSIVE AGENT a) Dr.FIXIT DR.Fixit R	NA			0.00
a	50.00	-do- in 1st floor	-do- in 1st floor	-do- in 1st floor	NA	805.25	1Sqm	40262.39
b	50.00	-do- in 2nd floor	-do- in 2nd floor	-do- in 2nd floor	NA	840.55	Sqm	42027.71
c	45.00	-do- in 3rd floor	-do- in 3rd floor	-do- in 3rd floor	NA	875.85	Sqm	39413.25

11	155.00	SPECIALISED INJECTION GROUTING WITH CEMENT AND FREE FLOW ADDITIVES: a]. Drilling of holes with power drilling machine to the required depth [12mm to 14mm dia holes] b]. Fixing of Rubber Nozzles with cement and quick setting, Rapid hardening compound putty - Rapidstrong qs or equivalent. c]. Grouting of holes with 140 PSI Grout pump with cement slurry mixing with Specialized Free flow, Non-shrink Grout additive - RAPIDSTRONG GROUT ADMIX (Armstrong) /POWER n GROUT ADMIX (EBT) / CEBEX 100 (Fosroc)/ ZORIGROUT GP1 (PMCC) / SIKAGROUT ANCHKOR NSQ (Sika) /WATERSHIELD GROUT ADMIXi.e., 250 Grams per bag of 50 Kgs Cement add required water to make slurry form. d]. After completion of grouting, Remove the Rubber nozzles e]. Later sealing of the hole with polymer cement putty - ROOFCRETE AR (Armstrong) / ZORIGROUT CMG (PMCC) / POWER n GUARD ARM (EBT) / WATERSHIELD AR / Fosroc NITOBOND AR + Cement. * FOR STRENTHENING AND SEAL THE POROSITY OF THE CONCRETE TO ARREST THE LEAKAGES, DAMPNESS, LEAKAGES OF CONSTRUCTION JOINTS: (FOR TERRACE /CEILING / RCC RETAINING WALLS BASEDMENT FLOORINGS / WATER TANKS / RESERVOIRS / TOILETS etc.,)	SPECIALISED INJECTION GROUTING WITH CEMENT AND FREE FLOW ADDITIVES: a]. Dr	SPECIALISED INJECTION GROUTING WITH CEMENT AND FRE	NA	185.31	Each	28723.05

12		Flooring with Non-skid red or white full body Ceramic floor tiles of size 450 x 450 mm and thickness between 7-8 mm 1st quality conforming to IS:13711, IS:13712, IS:13630 (Parts 1 to 15) of any colour and finish in all series & shades and designs (as per manufacture specification), set over base coat of cement mortar (1:6) 20mm thick over CC bed already laid or RCC roof slab, including neat cement slurry of honey like consistency spread @ 3.30 kgs per sq.m. jointed with neat cement to full depth mixed with pigment of matching shade, including cost and conveyance of all materials like flooring slab, cement, sand and water etc., complete, for finished item of work. (Note: Unless otherwise laying of flooring is finished, no pre-payment shall be made for the tiles against supply).	Flooring with Non-skid red or white full body Ceramic floor tiles of size	Flooring with Non-skid red or white full body Cer	NA		1Sqm	
a	130.00	-do-in 1st floor	-do-in 1st floor	-do-in 1st floor	NA	1144.47	1Sqm	148781.13
b	130.00	-do-in 2nd floor	-do-in 2nd floor	-do-in 2nd floor	NA	1207.21	1Sqm	156936.97
c	65.00	-do- in 3rd floor	-do- in 3rd floor	-do- in 3rd floor	NA	1269.94	1Sqm	82546.41
13		Finishing the sides of walls with glazed red or white full body ceramic wall tiles of size 300 x 450 mm / 320 mm x 400 mm and thickness 6 mm 1st quality conforming to IS:13711, IS:13712, IS:13630 (Parts 1 to 15) of approved colour and finish in all shades and designs including pointing the joints with the same colour of cement by mixing the same colour pigment in white cement and over a bed of C.M.(1:3), 12 mm thick & Cement slurry of 33 Kg/10sq.m shall be used for fixing bed tiles including cost and conveyance of all materials, curing, incidental charges etc., complete (No separate plastering shall be paid to the walls). (Note: Unless otherwise laying of flooring is finished, no pre-payment shall be made for the tiles against supply).	Finishing the sides of walls with glazed red or white full body ceramic wa	Finishing the sides of walls with glazed red or w	NA			0.00
a	85.00	-do-in 1st floor	-do-in 1st floor	-do-in 1st floor	NA	722.98	1Sqm	61453.59

b	85.00	-do- in 2nd floor	-do- in 2nd floor	-do- in 2nd floor	NA	738.93	1Sqm	62808.84
c	45.00	-do- in 3rd floor	-do- in 3rd floor	-do- in 3rd floor	NA	754.87	1Sqm	33969.22
14	500.00	Supplying and fixing in position M.S Ornamental grills for windows and ventilators or for veranda openings using M.S. Flats, square rods, angles sheets etc., of approved design including necessary cuttings, bending fabrication, welding, grinding and finishing smooth including painting the grills with Two coats with Synthetic enamel paint over a Primary coat (Red oxide metal primer) (total three coats) of approved make and colour including cost of making the holes into RCC or masonry works and making good the same wherever necessary, including cost and conveyance of all materials, incidental charges etc., complete.	Supplying and fixing in position M.S Ornamental grills for windows and ven	Supplying and fixing in position M.S Ornamental g	1002	134.34	kg	67170.00
15	50.00	Providing weld mesh enclosures made out of M.S ' L ' angles of size 25 x 25 x 5mm for outer frame, M.S. ' T 'section of size 25 x 25 x 5mm for central vertical mullion and fixing the 6 G x 10 G weld mesh with openings of size 75mm x 25mm to the frame by using M.S. flat of size 25 x 5mm by means of M.S. bolts and nuts including fixing the frame in position by making holes in walls / R.C.C. fin walls and making good the same and finishing smooth etc., complete as directed during the execution.	Providing weld mesh enclosures made out of M.S ' L ' angles of size 25 x 25	Providing weld mesh enclosures made out of M.S ' L	NA	2680.78	1Sqm	134039.00

16		Providing and fixing factory made uPVC white colour sliding glazed window up to 1.50 m in height dimension comprising of uPVC multi-chambered frame with in-built roller track and sash extruded profiles duly reinforced with 1.60 ± 0.2 mm thick galvanized mild steel section made from roll forming process of required length (shape & size according to uPVC profile), appropriate dimension of uPVC extruded glazing beads and uPVC extruded interlocks, EPDM gasket, wool pile, zinc alloy (white powder coated) touch locks with hook, zinc alloy body with single nylon rollers (weight bearing capacity to be 40 kg), G.I fasteners 100 x 8 mm size for fixing frame to finished wall and necessary stainless steel screws, etc.. Profile of frame & sash shall be mitred cut and fusion welded at all corners, including drilling of holes for fixing hardware's and drainage of water etc. After fixing frame the gap between frame and adjacent finished wall shall be filled with weather proof silicon sealant over backer rod of required size and of approved quality, all complete as per approved drawing& direction of Engineer-in-Charge inclusive of cost of Single / double glass panes, wire mesh and silicon sealant . Note: For uPVC frame and sash extruded profiles minus 5% tolerance in dimension i.e. in depth & width of profile shall be acceptable. Variation in profile dimension in higher side shall be accepted. But no extra payment on this account shall be made.	Providing and fixing factory made uPVC white colour sliding glazed window u	Providing and fixing factory made uPVC white colou	NA			0.00

a	70.00	-do-Three track three panels sliding window with fly proof SS wire mesh (Two nos. glazed & one no. wire mesh panels) made of (small series) frame 92 x 44 mm & sash 32 x 60 mm both having wall thickness of 1.9 ± 0.2 mm and single glazing bead of appropriate dimension (Area of window upto 1.75 sqm).	-do-Three track three panels sliding window with fly proof SS wire mesh (T	-do-Three track three panels sliding window with	NA	9640.35	1Sqm	674824.50
17		Providing and fixing factory made solid Wood Polymer Composite (WPC) single extruded Door Frame section of size with encapsulation of 8MM rigid layer on all the six surfaces. The door frame will have a rebat of 32MM.	Providing and fixing factory made solid Wood Polymer Composite (WPC) single	Providing and fixing factory made solid Wood Polym	NA			0.00
a	130.00	-do- door Frame section of 63.5x100 MM . The two Vertical members are to be joined together with the horizontal member using 8x75 MM long MS Star full thread screws to be used with reverse forward speed control hand drilling machine. The ready/assembled door frame is fixed to the wall using hold fast or bolt fasteners. A minimum of 4 No.s of screws to be provided for each vertical member & minimum 2no.s for horizontal member.	-do- door Frame section of 63.5x100 MM . The two Vertical members are to	-do- door Frame section of 63.5x100 MM . The two	NA	1072.22	Rmt	139388.60
18	45.00	Providing and fixing 28 -30 MM thick solid Wood Polymer Composite(WPC) single extruded door shutter with 3MM top and bottom rigid layer with an overall density of 750kg/Cum. It will be fixed to the frame using 3 inch /4 inch hinges. A minimum of 4 hinges will be required for fixing the door with the frame.	Providing and fixing 28 -30 MM thick solid Wood Polymer Composite(WPC) sing	Providing and fixing 28 -30 MM thick solid Wood Po	NA	3950.40	1Sqm	177748.25
19	15.00	Supplying & Fixing Orissa Pan white glazed W.C of size 580 x 440 mm x260mm 1st quality ISI marked confirming to IS:2556-Part-3-1981 with "P" or "S" trap ISI Mark or equivalent brand approved by the department.	Supplying & Fixing Orissa Pan white glazed W.C of size 580 x 440 mm x260mm	Supplying & Fixing Orissa Pan white glazed W.C of	NA	1828.45	Each	27426.75

20	15.00	Supplying and Fixing European Water Closet of 1st quality confirming to IS:2556-Part-2-1973 of white glazed with 'S' trap with ISI mark or equivalent brand approved by the department	Supplying and Fixing European Water Closet of 1st quality confirming to IS:	Supplying and Fixing European Water Closet of 1st	NA	2160.51	Each	32407.65
21	20.00	Supplying & Fixing white glazed flat back half stall urinals 590 x 375 x 390 mm 1st quality confirming to IS:2556-1995 with standard C.P. Spreader of overall size 95 x 95 x 57 mm confirming to IS:2556 - Part 6, Sec-6-1974 fixed with screws complete Indian make with ISI mark or equivalent approved by the department.	Supplying & Fixing white glazed flat back half stall urinals 590 x 375 x 39	Supplying & Fixing white glazed flat back half sta	NA	3260.05	Each	65201.00
22	10.00	Supplying & Fixing Indian make Flat Back Wash Hand Basin of size 550 x 400 mm - Single C.P. Pillar cock 1st quality confirming to IS:2556-Part-4:1972 with ISI mark or equivalent approved by the department, with waste fittings like rubber plug, chain, 32 mm nominal size C.P. Fitting with parallel pipe thread confirming to IS:2963-1979 and fitted with 15 mm nominal bore Chromium Plated Pillar Tap of 1st quality Indian make 400 grams complete with standard CI brackets including wooden block	Supplying & Fixing Indian make Flat Back Wash Hand Basin of size 550 x 400	Supplying & Fixing Indian make Flat Back Wash Han	NA	2011.08	Each	20110.80
23	15.00	Supplying and Fixing best Indian make plastic seat and lid for European water closets with rubber or plastic Buffers as per IS 2548-1996	Supplying and Fixing best Indian make plastic seat and lid for European wa	Supplying and Fixing best Indian make plastic sea	NA	957.88	Each	14368.20
24	15.00	Supply & fixing of 10 Litres capacity Single Flush PVC low level systern with internal components & short bend.	Supply & fixing of 10 Litres capacity Single Flush PVC low level systern wi	Supply & fixing of 10 Litres capacity Single Flush	NA	1638.57	each	24578.55
25	10.00	Supplying & fixing stainless steel sink size 36" x 18" (914.4x457.2mm)	Supplying & fixing stainless steel sink size 36" x 18" (914.4x457.2mm)	Supplying & fixing stainless steel sink size 36" x	NA	8035.23	Each	80352.30

26	120.00	Supply of Anodised Alluminium tower bolts 10mm x 150mm long with ISI Mark IS 204	Supply of Anodised Alluminium tower bolts 10mm x 150mm long with ISI Mark I	Supply of Anodised Alluminium tower bolts 10mm x 1	NA	101.76	Each	12211.20
27	60.00	Supplying of mild steel (Powder coated) Aldrop 200mm long (IS 2681)	Supplying of mild steel (Powder coated) Aldrop 200mm long (IS 2681)	Supplying of mild steel (Powder coated) Aldrop	NA	124.25	Each	7455.00
28	120.00	Supply of Anodised Alluminium Door Handles (IS:208) 150mm Long	Supply of Anodised Alluminium Door Handles (IS:208) 150mm Long	Supply of Anodised Alluminium Door Handles (IS:20	NA	143.53	Each	17223.60
29		Supply & laying of PVC/SWR Pipes & fittings (as per ISI Standards) 6 Kg/Cm2(Type-B) including labour charges for laying, fixing and commissioning the PVC pipes including couplers/bends/tees etc., any dia including fixing necessary fittings like bends, plugs, couplers, junctions, tees,etc., with solvent jointing as per standard practice.	Supply & laying of PVC/SWR Pipes & fittings (as per ISI Standards) 6 Kg/Cm2	Supply & laying of PVC/SWR Pipes & fittings (as pe	NA			
a	50.00	-do- 75 mm dia Single Socket pipe	-do- 75 mm dia Single Socket pipe	-do- 75 mm dia Single Socket pipe	NA	261.54	Rmt	13077.00
b	50.00	-do 110 mm dia Single socket pipe	-do 110 mm dia Single socket pipe	-do 110 mm dia Single socket pipe	NA	395.07	Rmt	19753.50
30		Supply and Fixing of Premium make CPVC Pipes and Fittings to meet the requirement of ASTM-D 2846 and are produced in CTS (Copper Tube Sizes 1/2" to 2" SDR 11 and 13.5 SDR pipes are made from identical CPVC compounds having the same physical Properties for Hot and Cold Water (IS 15778:2007)	Supply and Fixing of Premium make CPVC Pipes and Fittings to meet the requi	Supply and Fixing of Premium make CPVC Pipes and F	NA			
a	50.00	-do-22.20 mm OD Pipe - SDR 11	-do-22.20 mm OD Pipe - SDR 11	-do-22.20 mm OD Pipe - SDR 11	NA	217.44	Rmt	10872.00
b	50.00	-do-28.60 mm OD Pipe - SDR 11	-do-28.60 mm OD Pipe - SDR 11	-do-28.60 mm OD Pipe - SDR 11	NA	268.86	Rmt	13443.00

31		Painting priming coat with ready mixed Cement primer (water thinnable) for plastered surface including cost and conveyance of all materials including brushes to have smooth finish as directed during execution.	Painting priming coat with ready mixed Cement primer (water thinnable) for	Painting priming coat with ready mixed Cement prim	1209 1201			
a	150.00	-do- Cement primer for interior grade - I for new work	-do- Cement primer for interior grade - I for new work	-do- Cement primer for interior grade - I for new	1209 1201	75.04	1Sqm	11256.58
b	150.00	-do- Cement primer for interior grade - I for old work	-do- Cement primer for interior grade - I for old work	-do- Cement primer for interior grade - I for old	1209 1201	50.03	1Sqm	7504.39
32		Painting with Acrylic emulsion paint interior grade with silicon additives having VOC (Volatile Organic Compound) content less than 50 grams/liter of approved brand and shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including cost and conveyance of all materials to work site and all operational, incidental, labour charges etc., complete for finished item of work as per SS 911 for internal walls.	Painting with Acrylic emulsion paint interior grade with silicon additives	Painting with Acrylic emulsion paint interior gra				
a	150.00	-do- Two coats for Internal walls for New plastered surface	-do- Two coats for Internal walls for New plastered surface	-do- Two coats for Internal walls for New plaste	911	128.18	1Sqm	19227.68
b	150.00	-do- Two coats for Internal walls for old plastered surface	-do- Two coats for Internal walls for old plastered surface	-do- Two coats for Internal walls for old plaste	911	85.46	1Sqm	12818.45
33	10.00	Providing weather proof course with Screeding concrete in CC(1:2:4), 25mm average thickness using 6 to 10mm nominal size HBG crushed metal chips, screeding duly embedding 24G chicken mesh with necessary overlap etc.., and finishing the surface neatly and rounding the edges at parapet walls, columns etc., including cost of chicken mesh, including cost of all materials and conveyance of all materials etc., complete as directed during execution.	Providing weather proof course with Screeding concrete in CC(1:2:4), 25mm a	Providing weather proof course with Screeding conc	NA	8242.29	1Cum	82443.51

34	260.00	Providing impervious coat to exposed RCC roof slab surface with CM (1:3), 20mm thick with 500 ml of liquid concentrated micronized cement water proof compound /100 ml of integral cement water proofing admixture complies with IS:2645-2003 of approved make per 50 kg bag of cement laid over roof when it is green including cost of all materials, conveyance charges of materials and all operational, incidental and labour charges for mixing mortar, laying, rendering smooth and thread lining, curing, rounding off juctions of wall and slab etc., complete for finished item.	Providing impervious coat to exposed RCC roof slab surface with CM (1:3),	Providing impervious coat to exposed RCC roof sl	NA	647.83	1Sqm	168435.80
35	3780.00	Specialised Five Layer System of WATERPROOFING TREATMENT to the terrace with following specifications	Specialised Five Layer System of WATERPROOFING TREATMENT to the terrace wit	Specialised Five Layer System of WATERPROOFIN G TRE	NA	652.33	1Sqm	2465807.40
		Providing and laying five layer water proofing cum heat insulation treatment (MIX GUARD HR5) over existing roof slab, all as directed by Engineer-in-charge and as per the following specification: Arresting roof leakage by providing five layer treatment with MIX GUARD HR5 – five layer system of FAB Chemicals or equivalent elastomeric water proofing and heat reflective coating comprising of the following:	Providing and laying five layer water proofing cum heat insulation treatmen	Providing and laying five layer water proofing cum	NA			0.00
		A.Surface preparation – Cleaning the whole area with wire brush. Chipping all loose/dead mortar thoroughly. Cleaning the entire area with high pressure water jetting to remove all loose particles/grease/oil/dust/dirt/curing compound etc. Surface cracks must be filled with Mix Build GP and wide cracks must be cut and repaired with Mix build SR polymer modified repair mortar. B) Application of Mix Guard HR5 – five layer system with brush.	A.Surface preparation – Cleaning the whole area with wire brush. Chipping	A.Surface preparation – Cleaning the whole area wi	NA			0.00

		1. First layer – MIX PRIME AC-100 Apply base prime coat using Mix Prime AC100 compound which is produced by mixing Mix Prime AC-100 with water and cement at the ratio 2:1:3 (Mix prime AC 100 : water : cement) by volume with a slow speed drill with paddle. This compound shall be applied with sufficient thickness to cover the holes/pores/cracks @ 1 lit/Sqm area (0.35 Lt of MIX Prime AC100/Sqm)	1. First layer – MIX PRIME AC-100 Apply base prime coat using Mix Prime AC1	1. First layer – MIX PRIME AC-100 Apply base prime	NA			0.00
		2. Second Layer – MIX MAT GFM 70 / 50 Mix mat GFM70/50 Synthetic fibre reinforced mesh shall be spread on the top of the primer/in mix with Mix prime AC100 in the wet condition and allow to dry for a period of 6 to 8 hours. A minimum overlap of 100 mm to be provided at the joints i.e. at 1.10 Sqm/Sqm. The Mix mat GFM Mesh shall confirm to the technical specification as per the manufacturers data sheet (40 Gram / Sqm as a weight)	2. Second Layer – MIX MAT GFM 70 / 50 Mix mat GFM70/50 Synthetic fibre rein	2. Second Layer – MIX MAT GFM 70 / 50 Mix mat GFM7	NA			0.00
		3. Third Layer – MIX PRIME AC Apply one coat of Mix Prime AC water based acrylic primer (with undiluted material) over the MIX mat GFM mesh @ 0.25 Kg/Sqm as a water tight primer in white colour and allow to dry for a period of 6 hours.	3. Third Layer – MIX PRIME AC Apply one coat of Mix Prime AC water based ac	3. Third Layer – MIX PRIME AC Apply one coat of Mi	NA			0.00
		4. Fourth layer – MIX GUARD HR (Base Coat) Apply one coat of Mix Guard HR acrylic based water proof and weather proof coating in white colour (with undiluted material) @ 0.50 kg/sq.m as a membrane on top of Mix prime AC and allow to dry for a period of 6 hours.	4. Fourth layer – MIX GUARD HR (Base Coat) Apply one coat of Mix Guard HR a	4. Fourth layer – MIX GUARD HR (Base Coat) Apply o	NA			0.00

		5. Fifth Layer – Mix Guard HR Extra (Top Coat) Apply one coat of Mix Guard Hr Extra acrylic based fibre reinforced water proofing and heat reflective membrane in white colour on top of Mix Guard HR base coat (With undiluted material) @ 0.50 kg/sq.m. And allow to dry the system for period of 24 hours to allow foot traffic.	5. Fifth Layer – Mix Guard HR Extra (Top Coat) Apply one coat of Mix Guard	5. Fifth Layer – Mix Guard HR Extra (Top Coat) App	NA			0.00
		Note: All the materials namely Mix Prime AC100, Mix Mat GFM70/50, Mix Prime AC, Mix Guard HR and Mix Guard HR Extra shall be procured for the entire work order quantity based on the consumption/coverage area as specified in the specification and shall be ensured by Engineer-in-charge. The Mix Guard HR5 layer system shall be carried out as per FAB Specifications.	Note: All the materials namely Mix Prime AC100, Mix Mat GFM70/50, Mix Prime	Note: All the materials namely Mix Prime AC100, Mi	NA			0.00
		Tensile strength : 6.00 N/mm2 (ASTM D412 – 87) Adhesion to substance : > 1.5 N/mm2 (ASTM D4541) for MIX PRIME AC100 slurry with HP tiles, cementitious substrate and subsequent layers. Appearance: White/Grey/Terracotta liquid components Dry film apperance : Joint free membrane Density : 1.3 gm/cc	Tensile strength : 6.00 N/mm2 (ASTM D412 – 87) Adhesion to substance : > 1	Tensile strength : 6.00 N/mm2 (ASTM D412 – 87) Adh	NA			0.00

		Tear strength : > 17 N/mm2 (ASTM D1004-76) Elongation at break : 200% for the system (ASTM D638) DFT of cured membrane : 1500 to 1700 microns Total Solids content: 68% + 2% . Water penetration : No leak at 7 bars +ve side (DIN 1048) Application temperature : 5 deg C to 50 deg C Touch dry: 2 hrs at 25 deg C Recoatable : 6-8 hrs at 25 deg C Full cure: 7 days.	Tear strength : > 17 N/mm2 (ASTM D1004-76) Elongation at break : 200% for t	Tear strength : > 17 N/mm2 (ASTM D1004-76) Elongat	NA			0.00
		OR						0.00
		SPECIALISED FIVE LAYER SYSTEM OF WATERPROOFING TREATMENT TO THE TERRACE WITH Roofcare-prc 5 Systems or equivalent (ROOFCARE PRC 5 (Armstrong) / ZORICOAT PFC 5 (PMCC)/ POWER SAC 5 L (EBT)/ WATERSHIELD 5 LWC.	SPECIALISED FIVE LAYER SYSTEM OF WATERPROOFING TREATMENT TO THE TERRACE WIT	SPECIALISED FIVE LAYER SYSTEM OF WATERPROOFIN G TRE	NA			0.00
		a). Ist Layer : Black coloured chemcial treatment : Providng and application of one coat of High bonding, flexible bituminous polyurethane blended bituminous coating with – Roofcare prc 5 systems Confiming to ASTM-G 154 -2000 or equavalent Ist Layer diluting with water at 1 : 1 ratio as a primer coat at a consumption of 200 ml per Sqm.	a). Ist Layer : Black coloured chemcial treatment : Providng and applicatio	a). Ist Layer : Black coloured chemcial treatment	NA			0.00
		b). IInd Layer : Providing and laying of Fibre Mesh 40 GSM, with 1 Mtr width and 50 mm overlap on the primed surface.	b). IInd Layer : Providing and laying of Fibre Mesh 40 GSM, with 1 Mtr widt	b). IInd Layer : Providing and laying of Fibre Mes	NA			0.00

		c). IIIrd Layer : Grey coloured coating : Providing and application of one coat of Acrylic rubberized elastomeric flexible waterproof grey coating with – Roofcare prc 5 systems ASTM-C 836 or equavalent or equavalent diluting with 50% of water at a consumption of 400 ml per Sqm.	c). IIIrd Layer : Grey coloured coating : Providing and application of one	c). IIIrd Layer : Grey coloured coating : Providin	NA			0.00
		d). IVth Layer : white colured coating : Providing and application of one coat of High solid, cold applied, Fibre reinforced acrylic elastomeric waterproof membrane off white coating –Roofcare prc 5 systems Confiming to ASTM-G 154 -2000 or equavalent coating (add the water upto 200ml) (Consumption of 350ml per Sqm).	d). IVth Layer : white colured coating : Providing and application of one c	d). IVth Layer : white colured coating : Providing	NA			0.00
		e). Vth Layer : super white reflective coating : Application of one coat of 100% pure acrylic solar reflective pure white coating with Roofcareprc 5 systems Confirming to ASTM -C 297 or equavalent solar refective coating diluting with 20% of water (Consumption of 300ml per Sqm).	e). Vth Layer : super white reflective coating : Application of one coat of	e). Vth Layer : super white reflective coating : A	NA			0.00
		Note : THE ABOVE TREATMENT WILL BE GUARANTEED FOR 5 YEARS			NA			0.00
TOTAL (Rupees Fifty Seven Lakhs Forty seven thousand five hundred seventy five and Paise seventeen only)								**5747575.17**

Digitally signed by
MANOHARAM BADDELI
Date: 24-10-2026
19:02:59