SMOKE EXTRACTION & STAIRCASE PRESSURIZATION ELECTRICAL PANEL SLD:
1. Dual redundant power supply with automatic transfer switch (ATS) complying with NFPA 92 and NBC 2016.
2. Fire rated electrical switchboard with 2-hour fire endurance rating (CWZ per BS 6387) for emergency smoke fan operation.
3. Dual speed starters (Star-Delta / Pole Changing) providing low speed for normal ventilation and high speed for fire smoke purge.
4. Manual override firefighter control panel (FFCP) located in the Central Fire Command Center.
5. Auto-activation upon duct smoke detector or sprinkler water flow switch confirmation.

Fan Feeder	Service / Location	Normal Speed kW	Emergency Smoke kW	Starter Type	Cable Type
F-SMK-01	Basement -1 Smoke Extract	11.0 kW (Low)	30.0 kW (High)	Dual Speed Star-Delta	Fire Survival 4C x 25
F-SMK-02	Basement -2 Smoke Extract	11.0 kW (Low)	30.0 kW (High)	Dual Speed Star-Delta	Fire Survival 4C x 25
F-PRS-01	Staircase 1 Pressurization	N/A	15.0 kW (Full)	Star-Delta Starter	Fire Survival 4C x 16
F-PRS-02	Staircase 2 Pressurization	N/A	15.0 kW (Full)	Star-Delta Starter	Fire Survival 4C x 16
F-LOB-01	Fire Lift Lobby Pressurization	N/A	11.0 kW (Full)	Direct On-Line (DOL)	Fire Survival 4C x 10

AMARAVATI GOVERNMENT COMPLEX · LEGISLATIVE ASSEMBLY		
DWG TITLE: BASEMENT SMOKE EXTRACTION & PRESSURIZATION PA		
DRAWING NO: SL-288 - SINGLE LINE DIAGRAM	REV: R1	SCALE: 1:100
CLIENT: AP CRDA / GOVT OF ANDHRA PRADESH	DATED: 28-09-2026	