ANDHRA PRADESH STATE CAPITAL CITY INFRASTRUCTURE PROJECT
ENGINEERING WORKING DRAWING · TENDER REF #999239 (IFB: 23/MD/CE-Assembly/AGICL/2026 , Dated: 28.09.2026)

GENERAL NOTES & CAD COORDINATION DATA:
? Drawing Code: 171020-LA-431 | Project: Amaravati Legislative Assembly Complex
? All dimensions are in millimeters (mm) unless noted otherwise.
? Grid lines reference Survey of India AP State Geodetic Coordinate Network.
? Coordinate Datum: WGS84 / UTM Zone 44N.
? Do not scale from drawing. Work to figured dimensions only.

STRUCTURAL COLUMN SCHEDULE & COORDINATE MATRIX

Col C1-A	M60 Grade	1200x1200mm	+18.50m Level
Col C1-B	M60 Grade	1200x1200mm	+18.50m Level
Shear W1	PT Flared	800mm Thk	+42.00m Level
Spire Leg A	Steel S355	Dia 1600mm	+120.0m Level
Spire Leg B	Steel S355	Dia 1600mm	+120.0m Level
Spire Apex	Aero Cone	Dia 800mm	+250.0m Level

AMARAVATI GOVERNMENT COMPLEX · LEGISLATIVE ASSEMBLY		
DWG TITLE: SPIRE BASE RING GIRDER STRUCTURAL ASSEMBLY		
DRAWING NO: 171020-LA-431	REV: R1	SCALE: 1:100
CLIENT: AGICL / GOVT OF ANDHRA PRADESH	DATE: 28-09-2026	