Tender Ref ID: 999239 | Notice No: 23/MD/CE-Assembly/AGICL/2026 , Dated: 28.09.2026
Estimated Contract Value: Rs. 3,62,94,39,875/- | Bid Closing: 29/10/2026 03:00 PM
File: Assembly Spire Work bid document 02-10-2026.pdf | Portal: https://tender.apeprocurement.gov.in

VOLUME I: INSTRUCTIONS TO BIDDERS (ITB) & CONTRACT CONDITIONS

SECTION 1 ? INSTRUCTIONS TO BIDDERS (ITB)

1.1 Scope of Bid:
AGICL issues this Standard Bidding Document for the Investigation, Design, Engineering, Procurement, Fabrication, and Construction of the Central Spire, Iconic Roof Shell, RCC Substructure & Superstructure for the Amaravati Legislative Assembly.

1.2 High-Rise Iconic Landmark Parameters:
? Spire Peak Height: +250.00 meters above ground level.
? Structural System: Hybrid core-outrigger system with inclined flared shear walls and 3D diagrid tubular structural steel spire.
? Foundation: Heavy raft foundation on bored cast-in-situ concrete piles socketed into bedrock.
? Formwork System: Automated self-climbing fair-finish express formwork system ensuring F4 architectural finish without plastering.

Tender Ref ID: 999239 | Notice No: 23/MD/CE-Assembly/AGICL/2026 , Dated: 28.09.2026
Estimated Contract Value: Rs. 3,62,94,39,875/- | Bid Closing: 29/10/2026 03:00 PM
File: Assembly Spire Work bid document 02-10-2026.pdf | Portal: https://tender.apeprocurement.gov.in

SECTION 2 · SPECIAL CONDITIONS FOR SPIRE ERECTION & WIND DYNAMICS

2.1 Structural Wind Dynamics & Aerodynamic Damping:
? Wind Tunnel Testing: Rigorous boundary layer wind tunnel testing conducted at RWDI adheres to ISO 6897 comfort benchmarks.
? Tuned Mass Damper (TMD): Supply, installation, and fine-tuning of a 35-Ton bidirectional pendulum mass damper installed at +210m level.
? Real-Time Monitoring: Continuous anemometer wind speed monitoring at crane boom levels (> 45 km/h requires immediate suspension of lifting).

2.2 Quality Assurance & Non-Destructive Testing (NDT):
? 100% Ultrasonic Testing (UT) & Magnetic Particle Inspection (MPI) on all full-penetration butt welds of the structural spire.
? Digital photogrammetric alignment tracking across all 24 erection stages with maximum allowable plumbness deviation of H/2000.

Tender Ref ID: 999239 | Notice No: 23/MD/CE-Assembly/AGICL/2026 , Dated: 28.09.2026
Estimated Contract Value: Rs. 3,62,94,39,875/- | Bid Closing: 29/10/2026 03:00 PM
File: Assembly Spire Work bid document 02-10-2026.pdf | Portal: https://tender.apeprocurement.gov.in

SECTION 3 · 3D BIM LEVEL 2 LOD 400 & AERODYNAMIC WATERPROOFING

3.1 3D Building Information Modeling (BIM):
? The contractor must maintain a federated LOD 400 BIM model incorporating structural rebar, post-tensioning tendons, spire steel nodes, and inclined lift shafts.
? Weekly automated 4D schedule simulation and clash detection reports must be presented at AGICL project review sessions.

3.2 Comprehensive Multi-Layer Waterproofing System:
? Substructure Raft: Pre-applied dual-layer SBS modified bituminous membrane (4mm thickness) with protective screed.
? Spire & Roof Terrace: High-build aliphatic polyurethane trafficable elastomeric membrane with 20-year leak-proof warranty.

Tender Ref ID: 999239 | Notice No: 23/MD/CE-Assembly/AGICL/2026 , Dated: 28.09.2026
Estimated Contract Value: Rs. 3,62,94,39,875/- | Bid Closing: 29/10/2026 03:00 PM
File: Assembly Spire Work bid document 02-10-2026.pdf | Portal: https://tender.apeprocurement.gov.in

SECTION 4 · FORM OF AGREEMENT & DISPUTE RESOLUTION

STATUTORY FORM OF CONTRACT AGREEMENT

This Agreement made this ___ day of _____ 2026, between AGICL (The Employer) of the one part, and M/s _____ (The Contractor) of the other part.

Tender Ref: #999239 | Notice: 23/MD/CE-Assembly/AGICL/2026 , Dated: 28.09.2026
Accepted Contract Value: INR _____

Dispute Resolution: Any dispute or divergence arising under this contract shall be referred to adjudication and arbitration under the Indian Arbitration and Conciliation Act, 1996 with venue at Amaravati / Vijayawada.

Employer Signature: _____ Contractor Signature: _____
Witness 1: _____ Witness 1: _____