		NIT No. 87 /SE-III/TTD/2026-27						
Name of Work:- Re-Construction of Sri Mahakailaseswara Temple at Dhommata Village, Siddipet District.								
SL. No.	**Estimate Quantity (only Figures)**	**Item Detailed Specification Description**	**Work Type eg. Earth Work, Electrical works.. etc (upto 200 Characters)**	**Item Short Description (upto 100 Characters)**	**APSS / Morth Cl. Number (upto 200 Characters)**	**Rate (INR) (Upto 2 Decimals)**	**UOM (upto 50 Characters)**	**Amount (INR) (Upto 2 Decimals)**
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
1	6.00	Demolition including stacking of serviceable materials and disposal of unserviceable materials within 100 metres lead - R.C.C. Work	Demolition including stacking of serviceable materials and disposal of unserviceable materials within 100 metres lead - R.C.C. Work	Demolition including stacking of serviceable materials and disposal of unserviceable materials withi	NA	3109.83	cum	18658.98
2	62.00	Earthwork excavation for foundations and depositing on bank for all lifts and with an initial lead of 10 m including all Operational, incidental ,labour charges such as shoring, sheeting, planking, strutting etc., complete for finished item of work. Manual means up to 3m depth.	Earthwork excavation for foundations and depositing on bank for all lifts and with an initial lead of 10 m including all Operational, incidental ,la	Earthwork excavation for foundations and depositing on bank for all lifts and with an initial lead	NA	262.03	cum	16245.86
3	14.00	Cement Concrete (1:4:8) using 40 mm (0.54 cu.m), 20 mm (0.27 cu.m) and 12 mm (0.09 cu.m) nominal size hard broken granite crushed metal from any source conforming to the relevant ISI standards for foundations etc., laid in layers of not more than 15 cm thick well compacted including curing, machine mixing, cost and conveyance of all materials etc., complete.	Cement Concrete (1:4:8) using 40 mm (0.54 cu.m), 20 mm (0.27 cu.m) and 12 mm (0.09 cu.m) nominal size hard broken granite crushed metal from any sour	Cement Concrete (1:4:8) using 40 mm (0.54 cu.m), 20 mm (0.27 cu.m) and 12 mm (0.09 cu.m) nominal si	NA	5270.61	cum	73788.54

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
4	0.00	Boring with Augar in all types other than rock for under reamed piles of the following diameters and depth as per standard specifications and using reaming tools to a size of 2.50 times the diameter of the bore and providing approved design mix VRCC M30 with 20mm maxmimum size graded HBG metal using necessary tremie pipe and tripod arrangement for full depth of a pile for placing concrete, removal of slurry etc., complete as per the drawings with necessary reinforcement , including machine mixing, placing with tremie pipe , curing, other incidental charges etc., complete but excluding cost of reinforecement and its fabrication charges which will be paid separately.	Boring with Augar in all types other than rock for under reamed piles of the following diameters and depth as per standard specification	Boring with Augar in all types other than rock for under reamed piles of the following diam	NA	0.00	0.00	0.00
0	0.00	Note : The design mix shall be got designed by furnishing the information required as per clause 19.1.1 &19.1.2 of IS 456-2000 by the contractor at his own cost and get approved from the competent authority before execution. The cement considered for above M30 grade concrete is 400 kgs/Cum and the rate is arrived accordingly in the estimate. After the mix is designed and approved, if there is any variation in the quantity of cement, over the cement content adopted in the estimate, the same will be considered and paid/recovered at estimate rate ± T.P (Either increae or decrease in quantity adopted in the estimate). Payment will not be made for variation in the quantity of other materials such as coarse & Fine aggregates	Note : The design mix shall be got designed by furnishing the information required as per clause 19.1.1 &19.1.2 of IS 456-2000 by th	Note : The design mix shall be got designed by furnishing the information required	NA	0.00	0.00	0.00

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
a	16.00	Double under reamed piles of 380mm dia and 10.00m length	Double under reamed piles of 380mm dia and 10.00m length	Double under reamed piles of 380mm dia and 10.00m length	NA	17943.81	Each pile	287100.96
5	46.00	Cement Concrete (1:2.5:5) -Grade M15 using 20 mm (0.54 cu.m) and 12 mm (0.36cu.m) nominal size hard broken granite crushed metal from any source conforming to the relevant ISI standards for foundations etc., laid in layers of not more than 15 cm thick well compacted including curing, ,machine mixing, cost and conveyance of all materials etc., complete.	Cement Concrete (1:2.5:5) -Grade M15 using 20 mm (0.54 cu.m) and 12 mm (0.36cu.m) nominal size hard broken granite crushed metal from any source con	Cement Concrete (1:2.5:5) -Grade M15 using 20 mm (0.54 cu.m) and 12 mm (0.36cu.m) nominal size hard	NA	6065.30	cum	279003.80
6	0.00	Supply and placing of M 25 Design Mix Concrete corresponding to IS 456 using concrete mixer using of 20 mm HBG crushed metal 0.530 cu.m (707 kg), 10 mm HBG crushed metal, 0.362 cu.m (471 kg), sand 0.407 cu.m (616 kg.) and cement 380 kg with water cement ratio of 0.48 (182.40 ltrs/ cu.m of CC) etc., to site and including sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, vibrating, laying concrete, curing etc., complete with cement from standard suppliers approved by the department including cost of centering and scaffolding using steel scaffolding pipes, jack props, wallers, foot plates, brackets, steel centering plates etc but excluding cost of steel and its fabrication charges for finished item of work (APSS No. 402).	Supply and placing of M 25 Design Mix Concrete corresponding to IS 456 using concrete mixer using of 20 mm HBG crushed metal 0.530 cu.m (707 kg),	Supply and placing of M 25 Design Mix Concrete corresponding to IS 456 using concrete mixer usin	308	0.00	0.00	0.00

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
0	0.00	Note : The design mix shall be got designed by furnishing the information required as per clause 19.1.1 &19.1.2 of IS 456-2000 by the contractor at his own cost and get approved from the competent authority before execution. The cement considered for above M25 grade concrete is 380 kg/cu.m and the rate is arrived accordingly in the estimate. After the mix is designed and approved, if there is any variation in the quantity of cement, over the cement content adopted in the estimate, the same will be considered and paid/recovered at estimate rate ± T.P (Either increase or decrease in quantity adopted in the estimate). Payment will not be made for variation in the quantity of other materials such as coarse & Fine aggregates.	Note : The design mix shall be got designed by furnishing the information required as per clause 19.1.1 &19.1.2 of IS 456-2000 by the contractor at hi	Note : The design mix shall be got designed by furnishing the information required as per clause 19.	309 310	0.00	0.00	0.00
a)	29.00	- do - for Raft& Columns footings	- do - for Raft& Columns footings	- do - for Raft& Columns footings	NA	10327.42	Cum	299495.18
b)	18.00	- do - for Plinth beams	- do - for Plinth beams	- do - for Plinth beams	309 310	13576.46	cum	244376.28
c)	16.50	- do - for Roof beam in1st floor	- do - for Roof beam in1st floor	- do - for Roof beam in1st floor	NA	13564.87	Cum	223820.36
d)	10.50	- do - for Roof beam in 2nd floor	- do - for Roof beam in 2nd floor	- do - for Roof beam in 2nd floor	NA	14100.69	Cum	148057.25

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
7	8.70	Providing High Yield Strength deformed (HYSD)/ Thermo mechanically treated (TMT) steel bars of below 36 mm Fe 500/Fe-500D/Fe550 grade (as per IS 1786 - 2008) of different diametres for RCC works, including labour charges for straightening, cutting, bending to required sizes and shapes, placing in position with cover blocks of approved materials and size and tying and lap splicing with binding wire of 18 SWG, forming grills for reinforcement work as per approved designs and drawings, including cost and conveyance of steel bars including all wastages such as over laps, couplings, chairs, spacer bars including cost and conveyance of binding wire, cover blocks and all incidental, operational, labour charges such as cutting, bending, placing in position, tying including sales and other taxes on all materials etc., complete for finished item of work in all floors. (APSS NO.126) (In the absence of 18G binding wire, 2 nos of 20G binding wire in tandem are to be strictly adhered). Note: Unless otherwise fabrication and placement of steel, no pre-payment shall be made against the supply of steel reinforcement (Major Steel Manufacturers including PSUs like SAIL, VSP STEEL, TATA, JINDAL PANTHER	Providing High Yield Strength deformed (HYSD)/ Thermo mechanically treated (TMT) steel bars of below 36 mm Fe 500/Fe-500D/Fe550 grade (as per IS 178	Providing High Yield Strength deformed (HYSD)/ Thermo mechanically treated (TMT) steel bars of belo	NA	82333.60	MT	716302.32

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
8	30.00	Providing weather proof course with Screeding concrete in CC(1:2:4), 25mm average thickness using 6 to 10mm nominal size HBG crushed metal chips, screeding duly embedding 24G chicken mesh with necessary overlap etc.., and finishing the surface neatly and rounding the edges at parapet walls, columns etc., including cost of chicken mesh, including cost of all materials and conveyance of all materials etc., complete as directed during execution.	Providing weather proof course with Screeding concrete in CC(1:2:4), 25mm average thickness using 6 to 10mm nominal size HBG crushed metal chips, scre	Providing weather proof course with Screeding concrete in CC(1:2:4), 25mm average thickness using 6	NA	8491.87	cum	254756.10
9	600.00	Providing impervious coat to exposed RCC roof slab surface with CM (1:3), 20mm thick with 500 ml liquid Concentrated Micronized Cement water proofing compound /100 ml Integral Cement Water proofing Admixture Complies with I.S. 2645-2003 of approved make per 50 kg bag of cement, laid over roof when it is green including cost and conveyance of all materials and all operational, incidental and labour charges for mixing mortar, laying, rendering smooth and thread lining curing, rounding off junctions of wall and slab etc., complete for finished item.	Providing impervious coat to exposed RCC roof slab surface with CM (1:3), 20mm thick with 500 ml liquid Concentrated Micronized Cement water proofing	Providing impervious coat to exposed RCC roof slab surface with CM (1:3), 20mm thick with 500 ml liq	NA	552.86	sqm	331716.00
10	600.00	Plastering in Cement Mortar (1:3) 12 mm thick using best river sand from approved quarry including cost and conveyance of all materials, screening, curing, rounding of corners, lift charges, incidental charges as directed during execution complying with standard specifications etc., complete	Plastering in Cement Mortar (1:3) 12 mm thick using best river sand from approved quarry including cost and conveyance of all materials, screening, c	Plastering in Cement Mortar (1:3) 12 mm thick using best river sand from approved quarry including	402	278.00	Sqm	166800.00

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
11	600.00	Painting Two coats for new walls with Acrylic emulsion paint exterior grade with silicon additives having VOC (Volatile Organic Compound) content less than 50 grams/ liter over a priming coat using cement primer exterior grade-2 (Total Three coats) of approved brand and shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including cost and conveyance of all materials to work site and all operational, incidental, labour charges etc., complete for finished item of work as per SS 911 for external walls.	Painting Two coats for new walls with Acrylic emulsion paint exterior grade with silicon additives having VOC (Volatile Organic Compound) content les	Painting Two coats for new walls with Acrylic emulsion paint exterior grade with silicon additives h	126/ IS 1786	255.68	Sqm	153408.00
12	137.00	Flooring with high polished granite 16 to 18 mm thick slabs up to 8'-00 (2.43 M) black colours set over base coat of cement mortar (1:8) 20 mm thick over CC bed already laid or RCC roof slab, including neat cement slurry of honey like consistency spread @ 3.3 kgs per sqm & jointed neatly with white cement paste mixed with pigment of matching shade to full depth, including cost & conveyance of all materials, seigniorage charges, labour charges for dressing of tiles etc., complete for finished item of work.	Flooring with high polished granite 16 to 18 mm thick slabs up to 8'-00 (2.43 M) black colours set over base coat of cement mortar (1:8) 20 mm thick	Flooring with high polished granite 16 to 18 mm thick slabs up to 8'-00 (2.43 M) black colours set	NA	3801.88	Sqm	520857.56
13	600.00	Supplying and fixing of stainles steel SS-304 grade tubes, sections, plates, sheets & pipes of all sizes & diameters etc., inlcuding cost and conveyance of all materials and labour charges for fabriction of stainless steel railing works using SS welding rods including buffing, polishing lacquar finishing, to present seamless finishing etc., complete as directed during execution.	Supplying and fixing of stainles steel SS-304 grade tubes, sections, plates, sheets & pipes of all sizes & diameters etc., inlcuding cost and convey	Supplying and fixing of stainles steel SS-304 grade tubes, sections, plates, sheets & pipes of all	NA	585.90	Kg	351540.00

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
14	0.00	Ornamental brick work with 2nd class bricks in C.M (1:5) (using brick bats and Madras terrace bricks), including cost and conveyance of all materials, labour charges, curing, lift charges etc., complete.	Ornamental brick work with 2nd class bricks in C.M (1:5) (using brick bats and Madras terrace bricks), including cost and conveyance of all materials,	Ornamental brick work with 2nd class bricks in C.M (1:5) (using brick bats and Madras terrace bricks	NA	0.00	0.00	0.00
a)	2.00	-do- in 1st floor	-do- in 1st floor	-do- in 1st floor	NA	12369.69	Cum	24739.38
b)	116.00	-do- In 2nd Floor	-do- In 2nd Floor	-do- In 2nd Floor	NA	12728.61	Cum	1476518.76
c)	60.00	-do- in 3rd floor	-do- in 3rd floor	-do- in 3rd floor	NA	13087.54	Cum	785252.40
d)	20.00	-do- in 4th floor	-do- in 4th floor	-do- in 4th floor	NA	13446.46	Cum	268929.20
15	0.00	1st class Ornamental plastering 1" to 1 1/4" thick with base plastering 1/2" to 3/4" in CM (1:3) and top finishing 1/2" thick with CM (1:2) to bring the required oramentation, fine renderring with neat cement including cost and conveyance of all materials, labour charges, all incidental and operational charges, curing,etc., complete. To the required shape and size as per the approved drawings and as per Silpi norms including preparation and fixing of precast pillars wherever necessary .	1st class Ornamental plastering 1" to 1 1/4" thick with base plastering 1/2" to 3/4" in CM (1:3) and top finishing 1/2" thick with CM (1:2) to bring	1st class Ornamental plastering 1" to 1 1/4" thick with base plastering 1/2" to 3/4" in CM (1:3) an	NA	0.00	0.00	0.00
a)	2.00	-do- in 1st floor	-do- in 1st floor	-do- in 1st floor	NA	2769.26	Sqm	5538.52
b)	2.00	-do- in 2nd floor	-do- in 2nd floor	-do- in 2nd floor	NA	3026.41	Sqm	6052.82

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
16	0.00	Special class Ornamental plastering 1" to 1 1/4" thick with base plastering 1/2" to 3/4" in CM (1:3) and top finishing 1/2" thick with CM (1:2) to bring the required ornamentation including fine rendering with neat cement including cost and conveyance of all materials, labour charges, all incidental and operational charges, curing,etc., complete. To the required shape and size as per the approved drawings and as per Silpi norms including preparation and fixing of precast pillars, Kudam, palakas, Vedika, Lathalu in Uthara Eluthakam, Pothikas, Nasigudu, Pushpa Puskala, adhishtanam wherever necessary (sand of fine varity is to be used).	Special class Ornamental plastering 1" to 1 1/4" thick with base plastering 1/2" to 3/4" in CM (1:3) and top finishing 1/2" thick with CM (1:2) to b	Special class Ornamental plastering 1" to 1 1/4" thick with base plastering 1/2" to 3/4" in CM (1:	NA	0.00	0.00	0.00
a)	210.00	-do- in 2nd floor	-do- in 2nd floor	-do- in 2nd floor	NA	3765.27	Sqm	790706.70
b)	150.00	-do- in 3rd floor	-do- in 3rd floor	-do- in 3rd floor	NA	4089.60	Sqm	613440.00
c)	60.00	-do- in 4th floor	-do- in 4th floor	-do- in 4th floor	NA	4413.92	Sqm	264835.20
17	0.00	Supply of Hard Black granite stones of various sizes from Kotappakonda quarry, Andhra Pradesh for different Sculpture works. The rate is including quarrying, wedging, cut in to shapes, loading at quarry, unloading at work site, including cost and conveyance of stones, from quarry to work spot, incidental charges, sales tax, surcharges etc., complete.	Supply of Hard Black granite stones of various sizes from Kotappakonda quarry, Andhra Pradesh for different Sculpture works. The rate is including qu	Supply of Hard Black granite stones of various sizes from Kotappakonda quarry, Andhra Pradesh for d	NA	0.00	0.00	0.00
a)	6400.00	-do- 1 to 20 Cft	-do- 1 to 20 Cft	-do- 1 to 20 Cft	NA	464.14	Cft	2970496.00
b)	6000.00	-do- 20 to 40 Cft	-do- 20 to 40 Cft	-do- 20 to 40 Cft	NA	481.14	Cft	2886840.00
c)	2180.00	-do- 40 to 60 Cft	-do- 40 to 60 Cft	-do- 40 to 60 Cft	NA	566.17	Cft	1234250.60

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
18	0.00	Labour charges for dressing and carving of temple vargams in black granite. The rate is including labour charges for rough dressing with fine palmana dressing, erection and jointing labour charges for both skilled and unskilled and cost of smithy materials and labours charges for preparation of smithy materials (wherever necessary the vargams should be polishing as directed by the incharge Sthapathy and approved drawings). But, excluding cost of black granite stone and jointing materials like cement and sand etc., complete for the following stone Vargams. Dressing to vargams using both machine cutting and manual dressing, finished item of work	Labour charges for dressing and carving of temple vargams in black granite. The rate is including labour charges for rough dressing with fine palmana	Labour charges for dressing and carving of temple vargams in black granite. The rate is including la	NA	0.00	0.00	0.00
a)	12700.00	ROUGH DRESSING (Chitravanam, Padma Jagathi, Upapeeta Kantam, Upapeeta Kapothakam, Adisthna Jagathi(Plain), Adisthna Padmajagathi in Mukhapatram, Adisthna Kumudakam, Adisthana Kantam Pattika, Vedika and Sthambavargam with plain(only Pothika)	ROUGH DRESSING (Chitravanam, Padma Jagathi, Upapeeta Kantam, Upapeeta Kapothakam, Adisthna Jagathi(Plain), Adisthna Padmajagathi in Mukhapatram, Adis	ROUGH DRESSING (Chitravanam, Padma Jagathi, Upapeeta Kantam, Upapeeta Kapothakam, Adisthna Jagathi(P	NA	113.37	Sft	1439799.00
b)	11800.00	ROUGH DRESSING (Uttaram Eludhakam, Kapothakam including Gudu, Kodangai above 1'-3" ht, Vyalam, Chadura Vattam& Konavattam Prastharam, Eludhakam inside beams, Inside, walls & roof).	ROUGH DRESSING (Uttaram Eludhakam, Kapothakam including Gudu, Kodangai above 1'-3" ht, Vyalam, Chadura Vattam& Konavattam Prastharam, Eludhakam inside	ROUGH DRESSING (Uttaram Eludhakam, Kapothakam including Gudu, Kodangai above 1'-3" ht, Vyalam, Chadu	NA	124.70	Sft	1471460.00
ii)	0.00	Palamana dressing : (various Stone Vargams)	Palamana dressing : (various Stone Vargams)	Palamana dressing : (various Stone Vargams)	NA	0.00	0.00	0.00

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
a)	250.00	Chitravanam	Chitravanam	Chitravanam	NA	552.09	Sft	138022.50
b)	445.00	Padmajagathi	Padmajagathi	Padmajagathi	NA	926.19	Sft	412154.55
c)	200.00	Upapeetam - kantam	Upapeetam - kantam	Upapeetam - kantam	NA	580.43	Sft	116086.00
d)	215.00	Upapeeta kapothakam	Upapeeta kapothakam	Upapeeta kapothakam	NA	1020.29	Sft	219362.35
e)	260.00	Adhishtana- padmajagathi Mukapatram	Adhishtana- padmajagathi Mukapatram	Adhishtana- padmajagathi Mukapatram	NA	1171.06	Sft	304475.60
f)	230.00	Adhishtana- Jagathi (plain)	Adhishtana- Jagathi (plain)	Adhishtana- Jagathi (plain)	NA	929.59	Sft	213805.70
g)	280.00	Adhishtana- kumudakam	Adhishtana- kumudakam	Adhishtana- kumudakam	1002	1020.29	Sft	285681.20
h)	315.00	Adhishtanam- kantam pattika	Adhishtanam- kantam pattika	Adhishtanam- kantam pattika	NA	1020.29	Sft	321391.35
i)	260.00	Vedika	Vedika	Vedika	NA	1020.29	Sft	265275.40
j)	2295.00	Ornamental Stambhavargam with vargams i. e. pothika, veerakantam, kantam,kudam, heeram, urutham, kalasam etc.,	Ornamental Stambhavargam with vargams i. e. pothika, veerakantam, kantam,kudam, heeram, urutham, kalasam etc.,	Ornamental Stambhavargam with vargams i. e. pothika, veerakantam, kantam,kudam, heeram, urutham, kal	NA	2361.39	Sft	5419390.05
k)	430.00	Uttaram, Eludhakaram	Uttaram, Eludhakaram	Uttaram, Eludhakaram	NA	1099.64	Sft	472845.20
l)	335.00	Kapothakam including Gudu above 1'- 3' height	Kapothakam including Gudu above 1'- 3' height	Kapothakam including Gudu above 1'- 3' height	NA	2361.39	Sft	791065.65
m)	255.00	Vyalam	Vyalam	Vyalam	NA	1400.06	Sft	357015.30
n)	1990.00	Inside walls and roof	Inside walls and roof	Inside walls and roof	NA	555.49	Sft	1105425.10
19	0.00	Door frame: Supply of granite stone door frame of required size and shape as per plan or as directed during execution of work , including cost and conveyance of stone, etc., complete.	Door frame: Supply of granite stone door frame of required size and shape as per plan or as directed during execution of work , including cost and co	Door frame: Supply of granite stone door frame of required size and shape as per plan or as directe	NA	0.00	0.00	0.00

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
a)	25.00	For Garbhalayam and Ardha mandapam stone door frame upto 7'-0" height	For Garbhalayam and Ardha mandapam stone door frame upto 7'-0" height	For Garbhalayam and Ardha mandapam stone door frame upto 7'-0" height	NA	340.10	Cft	8502.50
b)	175.00	For Garbhalayam and Ardha mandapam stone door frame above 7'-0" height	For Garbhalayam and Ardha mandapam stone door frame above 7'-0" height	For Garbhalayam and Ardha mandapam stone door frame above 7'-0" height	NA	396.78	Cft	69436.50
20	300.00	Labour charges for Dressing stone door frame 5 line Palmana instead of fine dressing and polishing and padmams at top & bottom. Nagabandham on Vertical Stones for Garbhalayam and Ardhamandapam	Labour charges for Dressing stone door frame 5 line Palmana instead of fine dressing and polishing and padmams at top & bottom. Nagabandham on Vertic	Labour charges for Dressing stone door frame 5 line Palmana instead of fine dressing and polishing	NA	572.49	Sft	171747.00
21	1.00	Fixing charges for door frame in position as per plan for Garbhalayam and Ardhamandapam stone door frame up to 7'-0" height	Fixing charges for door frame in position as per plan for Garbhalayam and Ardhamandapam stone door frame up to 7'-0" height	Fixing charges for door frame in position as per plan for Garbhalayam and Ardhamandapam stone door f	NA	2040.57	Each set	2040.57
22	2.00	Fixing charges for door frame in position as per plan for Garbhalayam and Ardhamandapam stone door frame above 7'-0" to 9'-0" height	Fixing charges for door frame in position as per plan for Garbhalayam and Ardhamandapam stone door frame above 7'-0" to 9'-0" height	Fixing charges for door frame in position as per plan for Garbhalayam and Ardhamandapam stone door f	NA	3990.45	Each set	7980.90

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
23	3.00	Supply of Black granite stone and carving of Somasutram of different types as directed by the incharge Sthapathy, including cost and conveyance of stones, and labour charges with fine dressing and polishing etc., complete.. For 3'-6" to 4'-6" length - Somasutram with Nasithala with Gomukham	Supply of Black granite stone and carving of Somasutram of different types as directed by the incharge Sthapathy, including cost and conveyance of s	Supply of Black granite stone and carving of Somasutram of different types as directed by the inch	NA	20156.30	Each	60468.90
24	7.00	Supply and fixing Brass stoopi with stoopi dandum,Bramharandram stone (Gandhapurai) including cost and conveyance of all materials and labour charges etc., complete. Upto 4'-0" height (16 to 18 gauge)	Supply and fixing Brass stoopi with stoopi dandum,Bramharandram stone (Gandhapurai) including cost and conveyance of all materials and labour charges	Supply and fixing Brass stoopi with stoopi dandum,Bramharandra m stone (Gandhapurai) including cost a	NA	5611.57	Rft	39280.99
25	0.00	Providing cement virgrahams using cement, fine sand, Iran bars, mesh, brick bats, flat tile pieces etc., including cost and conveyance of all materials, labour charges, etc., complete	Providing cement virgrahams using cement, fine sand, Iran bars, mesh, brick bats, flat tile pieces etc., including cost and conveyance of all materia	Providing cement virgrahams using cement, fine sand, Iran bars, mesh, brick bats, flat tile pieces e	NA	0.00	0.00	0.00
a)	106.00	Standing posture -Two hands vigraham 2'-0" to 4'-0" height	Standing posture -Two hands vigraham 2'-0" to 4'-0" height	Standing posture -Two hands vigraham 2'-0" to 4'-0" height	NA	1932.87	Rft	204884.22
b)	90.00	Standing posture -Four hands vigraham 2'-0" to 4'-0" height	Standing posture -Four hands vigraham 2'-0" to 4'-0" height	Standing posture -Four hands vigraham 2'-0" to 4'-0" height	NA	2221.95	Rft	199975.50
c)	30.00	Sitting posture -Two hands vigraham 2'-0" to 4'-0" height	Sitting posture -Two hands vigraham 2'-0" to 4'-0" height	Sitting posture -Two hands vigraham 2'-0" to 4'-0" height	NA	2255.96	Rft	67678.80

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)
d)	40.00	Sitting posture -Four hands vigraham 2'-0" to 4'-0" height	Sitting posture -Four hands vigraham 2'-0" to 4'-0" height	Sitting posture -Four hands vigraham 2'-0" to 4'-0" height	NA	2528.04	Rft	101121.60
26	0.00	Supply and fixing of Scaffolding to structure oranamental works and sculpture works including cost and conveyance of all materials such as casurina poles, bamboos, country wood planks, nails and coir puri to provide working plat form covered with coconut leaves mats to protect the working item from sun rays and rains and also provided ladder up to roof level strongly. After completion of work scaffolding should be removed carefully as directed during exectuion etc., complete.	Supply and fixing of Scaffolding to structure oranamental works and sculpture works including cost and conveyance of all materials such as casurina p	Supply and fixing of Scaffolding to structure oranamental works and sculpture works including cost	NA	0.00	0.00	0.00
a)	3670.00	up to 20'-0" feet	up to 20'-0" feet	up to 20'-0" feet	NA	14.96	Sft	54903.20
b)	4130.00	20'-0" to 40'-0 feet	20'-0" to 40'-0 feet	20'-0" to 40'-0 feet	NA	13.72	Sft	56663.60
c)	1500.00	40'-0" to 60'-0 feet	40'-0" to 60'-0 feet	40'-0" to 60'-0 feet	NA	12.47	Sft	18705.00
Rupees Two crore ninety eight lakh ten thousand one hundred seventy one only								**₹ 2,98,10,171.00**

Digitally signed by
MANOHARAM BADDELI
Date: 23-10-2026
16:37:07