SCHEDULE-A

Name of the Work:- Construction of two rooms/ one room and renovation of existing rooms for SG MPL HS ANKASANI CHERUVU for the establishment of Autism Centers in Konaseema District

Estimate Cost:- Rs. 40.00 lakhs

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
1	2.030	Earth work excavation for foundations and depositing on bank for all lifts and with an initial lead of 10m including all operational, incidental, labour charges such as shoring, sheeting, planking, strutting etc., complete for Ordinary Soils finished item of work as per SS NO. 20-B for finished item of work	Earth work excavation for foundations and depositing	Earth work excavation for foundations and depositing	APSS No	254.34	cum	516.00
2	6.410	Sand filling in trenches, sides of foundations and basement with initial lead in layers not exceeding 15cm thick consolidating each deposited layer by watering and ramming including cost and conveyance of water to work site and all operational, incidental, labour charges, hire charges of T&P etc., complete for finished item of work	Sand filling in trenches, sides of foundations and basement	Sand filling in trenches, sides of foundations and basement	APSS No	447.39	cum	2868.00
3	2.560	Plain Cement Concrete (1:4:8) using 40 MM nominal size SS 5 hard broken granite metal including cost and conveyance of all materials like cement, fine aggregate (sand), coarse aggregate, water etc., to site and including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc., complete for finished item of work for finished item of work.	Plain Cement Concrete	Plain Cement Concrete	APSS No	4622.73	cum	11834.00
4	1.880	Brick masonry in CM (1:6) with bricks of traditional size 23 x 11 x 7 cm 2nd class including cost and conveyance of all materials and all labour charges etc., complete including curing charges for finished item of work for Basement.	Brick masonry in CM (1:6) with bricks of traditional size 23 x 11 x 7 cm 2nd class	Brick masonry in CM (1:6) with bricks of traditional size 23 x 11 x 7 cm 2nd class	APSS No	7554.15	cum	14202.00
5	8.130	Normal Plastering with CM (1:5), 12mm thick including cost and conveyance of all materials and all labour charges etc., complete for walls including scaffolding charges and curing charges etc., complete for finished item of work.	Normal Plastering with CM (1:5), 12mm thick	Normal Plastering with CM (1:5), 12mm thick	APSS No	362.12	sqm	2944.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
6	16.470	Plastering with CM (1:5), 20mm thick including cost and conveyance of all materials and all labour charges etc., complete for walls.	Plastering with CM (1:5), 20mm thick	Plastering with CM (1:5), 20mm thick	APSS No	376.36	sqm	6199.00
7	12.000	Supplying and fixing stainless steel hand railing, balustrade etc using 304 or 202 grade stainless steel pipes of 50 mm dia nominal bore for hand railing at 3'0" high from ground level and 40 mm dia nominal bore for vertical supports placed at 5'0" c/c and two numbers 25 mm dia nominal bore for horizontal pipes placed below hand railing pipe as per the approved drawing including cost and conveyance of all materials buffing charges polishing charges etc	Supplying and fixing stainless steel hand railing	Supplying and fixing stainless steel hand railing	APSS No	9051.58	Rmt	108619.00
8	59.920	Earth work excavation for foundations and depositing on bank for all lifts and with an initial lead of 10m including all operational, incidental, labour charges such as shoring ,sheeting, planking, strutting, etc. complete for finished item of work including seigniorage excluding dewatering charges	Earth work excavation for foundations and depositing	Earth work excavation for foundations and depositing	APSS No	254.34	Cum	15240.00
9	7.190	Plain Cement Concrete (1:4:8) using 40 MM nominal size SS 5 hard broken granite metal including cost and conveyance of all materials like cement, fine aggregate (sand), coarse aggregate, water etc., to site and including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc., complete for finished item of work for finished item of work.	Plain Cement Concrete	Plain Cement Concrete	APSS No	4622.73	Cum	33237.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
10	8.130	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403). Footings	VRCC M- 20 Nominal mix for Footings	VRCC M- 20 Nominal mix for Footings	APSS No	9491.48	Cum	77166.00
11	7.000	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403). Plinth Beam	VRCC M- 20 Nominal mix for Plinth Beam	VRCC M- 20 Nominal mix for Plinth Beam	APSS No	11877.39	Cum	83142.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
12	4.850	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403). Columns	VRCC M- 20 Nominal mix for Columns	VRCC M- 20 Nominal mix for Columns	APSS No	11516.08	Cum	55853.00
13	1.610	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403). Lintel & Sill level beam	VRCC M- 20 Nominal mix for Lintel & Sill level beam	VRCC M- 20 Nominal mix for Lintel & Sill level beam	APSS No	11559.26	Cum	18610.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
14	7.000	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403). Roof Beam	VRCC M- 20 Nominal mix for Roof Beam	VRCC M- 20 Nominal mix for Roof Beam	APSS No	10194.46	Cum	71361.00
15	1.160	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403). Sunshade & Chajja	VRCC M- 20 Nominal mix for Sunshade & Chajja	VRCC M- 20 Nominal mix for Sunshade & Chajja	APSS No	13426.80	Cum	15575.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
16	15.760	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403). 125 mm thick slab	VRCC M- 20 Nominal mix for 125 mm thick slab	VRCC M- 20 Nominal mix for 125 mm thick slab	APSS No	9945.64	Cum	156743.00
17	3.150	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403). 175 mm thick waist slab	VRCC M- 20 Nominal mix for 175 mm thick waist slab	VRCC M- 20 Nominal mix for 175 mm thick waist slab	APSS No	9112.04	Cum	28703.00
18	8.810	Brick masonry in CM (1:6) with bricks of traditional size 23 x 11 x 7 cm 2nd class including cost and conveyance of all materials and all labour charges etc., complete including curing charges for finished item of work for Basement.	Brick masonry in CM (1:6) with bricks of traditional size 23 x 11 x 7 cm 2nd class	Brick masonry in CM (1:6) with bricks of traditional size 23 x 11 x 7 cm 2nd class	APSS No	7554.15	Cum	66552.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
19	19.900	Filling with sand in trenches, sides of foundations and basement with initial lead in layers not exceeding 15 cm thick, consolidating each deposited layer by watering and ramming including cost and conveyance of water to work site and all operational, incidental, labour charges, hire charges of T & P etc., complete for finished item of work. (APSS NO. 309 & 310)	Filling with sand in trenches, sides of foundations and basement	Filling with sand in trenches, sides of foundations and basement	APSS No	447.39	Cum	8903.00
20	40.690	Brick masonry in CM (1:8) with bricks of traditional size 23 x 11 x 7 cm 2nd class including cost and conveyance of all materials and all labour charges etc., complete for finished item of work for Superstructure.	Brick masonry in CM (1:8) with bricks of traditional size 23 x 11 x 7 cm 2nd class	Brick masonry in CM (1:8) with bricks of traditional size 23 x 11 x 7 cm 2nd class	APSS No	7967.29	Cum	324189.00
21	141.490	Ornamental plastering to ceiling with CM (1:3), 12mm thick including cost and conveyance of all materials and all labour charges etc., complete.	Ornamental plastering to ceiling with CM (1:3), 12mm thick	Ornamental plastering to ceiling with CM (1:3), 12mm thick	APSS No	387.39	sqm	54812.00
22	180.640	Plastering with CM 2 coats, 12mm thick, base coat in CM (1:6), 8mm thick and top coat in CM (1:4), 4mm thick with sponze finishing including cost and conveyance of all materials and all labour charges etc., complete for walls.	Plastering with CM 2 coats, 12mm thick, base coat in CM (1:6), 8mm thick and top coat in CM (1:4), 4mm thick with sponze	Plastering with CM 2 coats, 12mm thick, base coat in CM (1:6), 8mm thick and top coat in CM (1:4), 4mm thick with sponze	APSS No	478.43	sqm	86424.00
23	143.260	Plastering with CM 2 coats, 20mm thick, base coat in CM (1:6), 16mm thick and top coat in CM (1:4), 4mm thick with sponze finishing including cost and conveyance of all materials and all labour charges etc., complete for walls.	Plastering with CM 2 coats, 20mm thick, base coat in CM (1:6), 16mm thick and top coat in CM (1:4), 4mm thick with sponze	Plastering with CM 2 coats, 20mm thick, base coat in CM (1:6), 16mm thick and top coat in CM (1:4), 4mm thick with sponze	APSS No	491.96	sqm	70478.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
24	120.680	Providing Impervious coat to exposed RCC roof slab surface with CM(1:3), 20mm thick with 1kg of water proof compound per bag of cement laid over roof when it is green including cost and conveyance of all materials all operational, incidental and labour charges for mixing mortar, laying, rendering smooth and thread lining, curing, rounding off junctions of wall and slab etc., complete for finished item of work	Providing Impervious coat to exposed RCC roof slab surface with CM(1:3), 20mm thick	Providing Impervious coat to exposed RCC roof slab surface with CM(1:3), 20mm thick	APSS No	385.88	sqm	46568.00
25	321.530	Painting to walls with two coats of acrylic emulsion paint of approved brand and shade over a base coat of approved cement primer grade I making 3 coats in all to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including cost and conveyance of all materials to work site and all operational, incidental, labour charges etc. complete for finished item of work as per SS 912 for internal walls	Painting to walls with two coats of acrylic emulsion paint for internal walls	Painting to walls with two coats of acrylic emulsion paint for internal walls	APSS No	139.29	sqm	44786.00
26	143.260	Painting to walls with two coats of acrylic emulsion paint of approved brand and shade over a base coat of approved cement primer of exterior grade-2 making 3 coats in all to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including cost and conveyance of all materials to work site and all operational, incidental, labour charges etc. complete for finished item of work as per SS 912 for external walls.	Painting to walls with two coats of acrylic emulsion paint for external walls.	Painting to walls with two coats of acrylic emulsion paint for external walls.	APSS No	180.82	sqm	25904.00
27	43.540	Painting to new iron works with two coats of synthetic enamel paint of approved brand and shade over one coat of red oxide primer of approved brand to give an even shade after thoroughly cleaning and sand papering the surface to remove all dirt and remains, including cost and conveyance of all materials to work site and all operational, incidental, labour charges etc. complete for finished item of work	Painting to new iron works with two coats of synthetic enamel paint	Painting to new iron works with two coats of synthetic enamel paint	APSS No	180.86	sqm	7875.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
28	130.622	Flooring with high polished granite slabs 16 to 18mm thick other than black set over base coat of cement mortar (1:8), 20 mm thick over CC bed already laid or RCC roof slab, including neat cement slurry of honey like consistency spread @ 3.3.kgs per sqm & jointed neatly with white cement paste mixed with pigment of matching shade to full depth, including cost of all materials like cement, sand water and tiles etc., complete, including seigniorage charges, labour charges for dressing of tiles etc., complete	Flooring with high polished granite slabs 16 to 18mm thick	Flooring with high polished granite slabs 16 to 18mm thick	APSS No	2344.14	sqm	306196.00
29	155.020	Providing skirting to internal walls to 15 cm height/ risers of steps with high polished granite slabs 16 to 18mm thick other than black, length equal to flooring stones set over base coat of CM (1:3) 12 mm thick with cement slurry of honey like consistency spread at the rate of 3.30 kgs per sqm and jointed with white cement paste mixed with pigment of matching shade to full depth, including cost of all materials like granite slabs, cement, sand and water etc.,	Providing skirting to internal walls to 15 cm height/ risers of steps with high polished granite slabs 16 to 18mm thick	Providing skirting to internal walls to 15 cm height/ risers of steps with high polished granite slabs 16 to 18mm thick	APSS No	2752.39	sqm	426675.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
30	10.080	Providing & Fixing of Openable Windows with Fly-mesh made of pre-painted steel (Base Steel as per IS 513 of 0.58 mm thick galvanized as per IS 277 with zinc of 150 GSM) primer coated with epoxy primer of 5-7 microns thick, finish painted with a polyester paint of 12-16 microns thick and back coated with 5-7 microns thick alkyd backer and the section for outer frame of 72 x 55mm, centre mullion of 72 x 50mm, section for fixed glass beading section of 12 x 12 mm and section for shutters of 48 x 25 mm and outer frame & mullion sections with rebate for glazed shutters, fly mesh and a 20 mm provision for guard bars/grills and fly mesh shutter section of 20 x 40 mm and the sections cut to length metre joined with corner bracket, centre mullions fixed with mullion cap, stay, handles, latch 2 Nos of heavy duty stainless steel pivot hinges per shutter and panelled with 0.5mm thick corrugated sheet and S.S. Mesh for fly mesh shutter (304 grade), fitted using rubber gaskets including fixing the windows in the concrete/masonry wall by means of self expanding screws, including 12mm Square guard bars with 4” (101.6mm) pitch, complete for finished item of work	Providing & Fixing of Openable Windows with Fly-mesh made of pre-painted steel	Providing & Fixing of Openable Windows with Fly-mesh made of pre-painted steel	APSS No	7369.07	sqm	74280.00
31	660.000	Supplying, fitting and placing Mild steel, Structural steel / MS Angles, using Doors, windows, ventilators, compound wall gates, grills, etc., including fabricating and fixing of steel works like Window Grills, Compound Wall Grills, Iron Doors, Windows including cost of welding rods, power charges, excluding cost of fixing in position, including cost and conveyance of all materials and all labour charges etc., complete	Supplying, fitting and placing Mild steel, Structural steel / MS Angles, using Doors, windows, ventilators, compound wall gates, grills, etc.	Supplying, fitting and placing Mild steel, Structural steel / MS Angles, using Doors, windows, ventilators, compound wall gates, grills, etc.	APSS No	111.34	Kg	73484.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
32	4400.000	Providing High Yield Strength Deformed (HYSD)/ Thermo Mechanically Treated (TMT) (Fe 415/ Fe 500 grade as per IS 1786 - -1979) of different diameters for RCC works , including labour charges for straightening, cutting, bending to required sizes and shapes, placing in position with cover blocks of approved materials and size and tying and lap-splicing with binding wire of 18 SWG, forming grills for reinforcement work as per approved designs and drawings, including cost and conveyance of steel bars, including all wastages such as overlaps, couplings, chairs, spacer bars including cost and conveyance of binding wire, cover blocks and all incidental, operational, labour charges such as cutting, bending, placing in position, tying including sales and other taxes on all materials etc., complete for finished item of work in all floors.(APSS No.126)	High Yield Strength Deformed (HYSD)/ Thermo Mechanically Treated (TMT) (Fe 415/ Fe 500 grade	High Yield Strength Deformed (HYSD)/ Thermo Mechanically Treated (TMT) (Fe 415/ Fe 500 grade	APSS No	69.81	Kg	307164.00
33	14.360	Earth work excavation for foundations and depositing on bank for all lifts and with an initial lead of 10m including all operational, incidental, labour charges such as shoring, sheeting, planking, strutting, etc. complete for finished item of work including seigniorage excluding dewatering charges etc as per SS - 20.B (APSS 308)	Earth work excavation for foundations and depositing on bank	Earth work excavation for foundations and depositing on bank	APSS No	254.34	Cum	3652.00
34	1.300	Plain Cement concrete (1:4:8) mix using 40 mm HBG metal with concrete mixture including coat and conveyance of all materials and all labour charges, machine mixing charges and curing charges etc., comlete for finished item of work.	Plain Cement concrete (1:4:8) mix using 40 mm HBG metal with concrete mixture	Plain Cement concrete (1:4:8) mix using 40 mm HBG metal with concrete mixture	APSS No	4622.73	Cum	6010.00
35	3.690	Sand filling in trenches, sides of foundations and basement with initial lead in layers not exceeding 15cm thick consolidating each deposited layer by watering and ramming including cost and conveyance of water to work site and all operational, incidental, labour charges, hire charges of T&P etc., complete for finished item of work	Sand filling in trenches, sides of foundations and basement	Sand filling in trenches, sides of foundations and basement	APSS No	447.39	Cum	1651.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
36	1.030	Plain Cement concrete (1:5:10) mix using 40 mm HBG metal with Concrete mixture for bed concrete (Levelleing Course) including cost and conveyance of all materials, all lbour charges and curing charges etc., complete for finished item of the work	Plain Cement concrete	Plain Cement concrete	APSS No	4467.39	Cum	4601.00
37	0.970	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403).For Column Footings	VRCC M- 20 Nominal mix for Footings	VRCC M- 20 Nominal mix for Footings	APSS No	9491.48	Cum	9207.00
38	1.270	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403). For Columns	VRCC M- 20 Nominal mix for Columns	VRCC M- 20 Nominal mix for Columns	APSS No	11516.08	Cum	14625.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
39	1.010	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403). For Plinth Beam	VRCC M- 20 Nominal mix for Plinth Beam	VRCC M- 20 Nominal mix for Plinth Beam	APSS No	11877.39	Cum	11996.00
40	0.920	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403). For Roof Level Beams	VRCC M- 20 Nominal mix for Lintel & Sill level beam	VRCC M- 20 Nominal mix for Lintel & Sill level beam	APSS No	10194.46	Cum	9379.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
41	1.930	RCC M- 20 Nominal mix (1:1.5:3) (Cement:fine aggregate: coarse aggregate) corresponding to Table 9 of IS 456 using 20 to 10 mm size graded machine crushed hard granite metal (coarse aggregate) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and including Seigniorage charges, sales & other taxes on all materials including all operational, incidental and labour charges such as machine mixing, laying concrete, curing etc.,complete but excluding cost of steel and its fabrication charges for finished item of work, but excluding centering, shuttering (APSS 402 & 403). For Roof Slab of 125 mm	VRCC M- 20 Nominal mix for Roof Slab of 125 mm thickness	VRCC M- 20 Nominal mix for Roof Slab of 125 mm thickness	APSS No	9945.64	Cum	19195.00
42	16.740	Providing impervious coat to exposed RCC roof slab surface with CM(1:3), 20mm thick with 1kg of water proof compound per bag of cement laid over roof when it is green including cost of all materials, seigniorage charges, excluding conveyance charges of materials and including all operational, incidental and labour charges for mixing mortar, laying, rendering smooth and thread lining, curing, rounding off junctions of wall and slab etc,, complete for	Providing impervious coat to exposed RCC roof slab surface with CM(1:3), 20mm thick	Providing impervious coat to exposed RCC roof slab surface with CM(1:3), 20mm thick	APSS No	385.88	sqm	6460.00
43	1.150	Brick masonry in CM (1:6) with bricks of traditional size 23 x 11 x 7 cm 2nd class including cost and conveyance of all materials and all labour charges etc., complete for finished item of work for Basement.	Brick masonry in CM (1:6) with bricks of traditional size 23 x 11 x 7 cm 2nd class	Brick masonry in CM (1:6) with bricks of traditional size 23 x 11 x 7 cm 2nd class	APSS No	7554.15	Cum	8687.00
44	8.330	Brick masonry in CM (1:8) with bricks of traditional size 23 x 11 x 7 cm 2nd class including cost and conveyance of all materials and all labour charges etc., complete for finished item of work for Superstructure.	Brick masonry in CM (1:8) with bricks of traditional size 23 x 11 x 7 cm 2nd class	Brick masonry in CM (1:8) with bricks of traditional size 23 x 11 x 7 cm 2nd class	APSS No	7967.29	Cum	66368.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
45	4.320	Providing and fixing factory made solid Wood Polymer Composite (WPC) single extruded Door Frame section of size with encapsulation of 8MM rigid layer on all the six surfaces. The door frame will have a rebat of 32MM. Door Frame section of 45x75 MM . The two Vertical members are to be joined together with the horizontal member using 8x50 MM long MS Star full thread screws to be used with reverse forward speed control hand drilling machine. The ready/assembled door frame is fixed to the wall using hold fast or bolt fasteners. A minimum of 4 no.s of screws to be provided for each vertical member & minimum 2no.s for horizontal member. Providing Wood Polymer Composite (WPC) solid, frostywhite single extruded factory made 2.44 mt x 1.22 mt boards in 18 MM thickness (Density 650 kg/Cum, Weight 35Kg). including labour charges for fixing the frame in position, fixing the board to the frame etc., complete for finished item of work	Providing and fixing factory made solid Wood Polymer Composite (WPC) single extruded Door	Providing and fixing factory made solid Wood Polymer Composite (WPC) single extruded Door	APSS No	4583.34	sqm	19800.00
46	27.110	Ornamental Plastering with CM (1:3), 12 mm thick for R.C.C. works including cost and conveyance of all materials and labour charges and curing charges etc complete for finished item of work	Ornamental Plastering with CM (1:3), 12 mm thick for R.C.C. works	Ornamental Plastering with CM (1:3), 12 mm thick for R.C.C. works	APSS No	387.39	sqm	10502.00
47	78.210	Normal Plastering with CM (1:5), 12 mm thick including cost and conveyance of all materials and labour charges and curing charges etc complete for finished item of work for superstructure	Normal Plastering with CM (1:5), 12 mm thick	Normal Plastering with CM (1:5), 12 mm thick	APSS No	478.43	sqm	37418.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
48	62.400	Painting to new plastered surfaces of interior walls with 2 coats of Plastic Emulsion Paint Asian/ Berger/ Nerolac/ Saicoat/Indocem or Equivalent and shade over Priming Coat with Cement Primer Waterbase Interior Gr- 1 Asian/ Berger/ Nerolac/ Saicoat/Indocem or Equivalenton New Plastered Surface making total 3 coats after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including cost and conveyance of all materials to work site and all operational, incidental, labour charges but excluding VAT etc, complete for finished item of work as per SS 911 for INTRNAL WALLS.	Painting to new plastered surfaces of interior walls with 2 coats of Plastic Emulsion Paint for INTRNAL WALLS.	Painting to new plastered surfaces of interior walls with 2 coats of Plastic Emulsion Paint for INTRNAL WALLS.	APSS No	139.29	sqm	8692.00
49	43.130	Painting to new walls with 2 coats of Plastic Emulsion Paint Asian/ Berger/ Nerolac/ Saicoat/Indocem or Equivalent and shade over Priming Coat with Cement Primer Waterbase exterior Gr- 2 Asian/ Berger/ Nerolac/ Saicoat/Indocem or Equivalenton New Plastered Surfaceafter thoroughly brushing the surface to remove all dirt and remains of loose powdered materials, including cost and conveyance of all materials to work site and all operational, incidental, labour charges but excluding VAT etc, complete for finished item of work as per SS 912 for external walls.	Painting to new walls with 2 coats of Plastic Emulsion Paint for external walls.	Painting to new walls with 2 coats of Plastic Emulsion Paint for external walls.	APSS No	180.82	sqm	7799.00
50	3.600	Painting to new wood works with two coats of approved synthetic enamel paint of approved brand and shade over one coat of wood primer of approved brand to give an even shade after thoroughly cleaning and sand papering the surface to remove all dirt and remains , including cost and conveyance of all materials to work site and all operational, incidental, labour charges etc. complete for finished item of work.	Painting to new wood works with two coats of approved synthetic enamel paint	Painting to new wood works with two coats of approved synthetic enamel paint	APSS No	192.62	sqm	693.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
51	12.030	Flooring with non-skid red or white fully body ceramic tiles of size 300 mm x 300 mm and thickness between 7 to 8 mm 1st quality conforming to IS 13711, IS 13712, IS 13630 (Parts 1 to 15) of any colour and finish in all shades and desings , set over base coat of cement mortar (1:8), 12 mm thick over CC bed already laid or RCC roof slab, including neat cement slurry of honey like consistency spread @ 3.3.kgs per sqm & jointed neatly with white cement paste to full depth mixed with pigment of matching shade, including cost of all materials like cement, sand water and tiles etc., .complete for finished item of work.	Flooring with non-skid red or white fully body ceramic tiles of size 300 mm x 300 mm and thickness	Flooring with non-skid red or white fully body ceramic tiles of size 300 mm x 300 mm and thickness	APSS No	1006.22	sqm	12105.00
52	30.910	Dadooing to walls with glazed red or white full body ceramic wall tiles of size 200 x 300 mm and thickness between 6-8 mm 1st quality, set over base coat of CM (1:3) 12 mm thick with cement slurry of honey like consistency spread at the rate of 3.30 kgs per sqm and jointed with white cement paste mixed with pigment of matching shade to full depth, including cost of all materials like tiles, cement, sand and water etc., complete for finished item of work.	Dadooing to walls with glazed red or white full body ceramic wall tiles of size 200 x 300 mm	Dadooing to walls with glazed red or white full body ceramic wall tiles of size 200 x 300 mm	APSS No	589.96	sqm	18236.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
53	1.000	Supplying and fixing 580 mm x 440 mm long Orissa pan white glazed Water Closet 1st qualityISI marked confirming to IS:2556-Part-3-1981 with "P" or "S" trap Hindware / Parryware / Neycer with brick masonry seat, CC squatting plate and fixing 12.70mm dia NP Push cock 1st quality , P trap or S trap of Indian W.C. shall be encased on CC (1:2:4) 150mm alround well above the joint to stop leakage at the joint etc., 10 Litres capacity Single Flush white PVC low level flushing system parryware, slimline with internal components and short bend including cost and conveyance of all materials to site, all labour charges, sales and other taxes on all materials etc., complete for finished item of work for all floorscomplete including cost and conveyance of all materials to site, cost of CC bed, labour charges and seigniorage charges etc., complete for finished item of work.	Supplying and fixing 580 mm x 440 mm long Orissa pan white glazed Water Closet	Supplying and fixing 580 mm x 440 mm long Orissa pan white glazed Water Closet	APSS No	4964.98	Nos	4965.00
54	1.000	Supply & fixing white glazed European water closet with variety as approved by Engineer-in-charge ,P" orS" trap with 4" CI outlet pipe of approved make,plastic seat and lid for EWC and rubber buffers as per ISI 2548 1963 with and 10 lits capacity PVC slimline low level flush tank of approved make with internal components and fixed with wooden gutties with required size nails,32mm dia short CP bend,12mm PVC Connections with brass union nuts and 12.70 mm (1/2") NP stop cock heavy duty (300 grams) complete including cost and conveyance of all materials to	Supply & fixing white glazed European water closet with variety	Supply & fixing white glazed European water closet with variety	APSS No	5709.15	Nos	5709.00
55	15.000	Supply and fixing of 28.60 MM OD pipe premium make Ashirvad/ Ajay/ Astral Flowguard or equivalent CPVC Pipes and Fittings SDR 13.5 to meet the requirement of ASTM-D 2846 and are produced in CTS (Copper Tube Sizes 1/2" to 2") for hot and cold water (IS 15778:2007) including cost and conveyance of all materials to site, labour charges for fixing etc., complete for finished item of work at all floor levels	Supply and fixing of 28.60 MM OD pipe premium	Supply and fixing of 28.60 MM OD pipe premium	APSS No	296.54	Rmt	4448.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
56	10.000	Supply and fixing of 12.70 mm N.P. bib tap Indian make heavy duty including cost and conveyance of tap to site and all labour charges etc., complete for finished item of work	Supply and fixing of 12.70 mm N.P. bib tap	Supply and fixing of 12.70 mm N.P. bib tap	APSS No	444.23	Nos	4442.00
57	15.000	Supply and fixing of 22.20 MM OD pipe premium make Ashirvad/ Ajay/ Astral Flowguard or equivalent CPVC Pipes and Fittings SDR 13.5 to meet the requirement of ASTM-D 2846 and are produced in CTS (Copper Tube Sizes 1/2" to 2") for hot and cold water (IS 15778:2007) including cost and conveyance of all materials to site, labour charges for fixing etc., complete for finished item of work at all floor levels	Supply and fixing of 22.20 MM OD pipe premium	Supply and fixing of 22.20 MM OD pipe premium	APSS No	253.36	Rmt	3800.00
58	10.000	Cost, supply and delivery of 110 mm diameter 6.00 kgs/cm2 test pressure Unplasticised PVC pipes suitable for potable water supplies conforming to IS 4985/200 (3rd revision) as per specifications including labour charges for laying, fixing and commissioning the PVC pipes including couplers/bends/tees etc., including fixing with necessary fittings like bends, plugsm couplers, juctions, tees etc., with solvent jointing as per standard practise including cost and conveyance of all materials to site for finished item of work	Cost, supply and delivery of 110 mm diameter 6.00 kgs/cm2	Cost, supply and delivery of 110 mm diameter 6.00 kgs/cm2	APSS No	323.80	Rmt	3238.00
59	10.000	Cost, supply and delivery of 75 mm diameter 6.00 kgs/cm2 test pressure Unplasticised PVC pipes suitable for potable water supplies conforming to IS 4985/200 (3rd revision) as per specifications including labour charges for laying, fixing and commissioning the PVC pipes including couplers/bends/tees etc., including fixing with necessary fittings like bends, plugsm couplers, juctions, tees etc., with solvent jointing as per standard practise including cost and conveyance of all materials to site for finished item of work	Cost, supply and delivery of 75 mm diameter 6.00 kgs/cm2	Cost, supply and delivery of 75 mm diameter 6.00 kgs/cm2	APSS No	186.71	Rmt	1867.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
60	1800.000	Providing High Yield Strength Deformed (HYSD)/ Thermo Mechanically Treated (TMT) / Mild steel (MS) steel bars (Fe 415/ Fe 500 grade as per IS 1786-1979) of different diameters for RCC works , including labour charges for straightening, cutting, bending to required sizes and shapes, placing in position with cover blocks of approved materials and size and tying and lap-splicing with binding wire of 18 SWG, forming grills for reinforcement work as per approved designs and drawings, including cost and conveyance of steel bars, including all wastages such as overlaps, couplings, chairs, spacer bars including cost and conveyance of binding wire, cover blocks and all incidental, operational, labour charges such as cutting, bending, placing in position, tying including sales and other taxes on all materials etc., complete for finished item of work in all floors.(APSS No.126)	High Yield Strength Deformed (HYSD)/ Thermo Mechanically Treated (TMT) / Mild steel (MS) steel bars (Fe 415/ Fe 500 grade	High Yield Strength Deformed (HYSD)/ Thermo Mechanically Treated (TMT) / Mild steel (MS) steel bars (Fe 415/ Fe 500 grade	APSS No	69.81	Kg	125658.00
61	25.000	Supply and fixing of 20 mm dia 2.10 mm thickness heavy grade with IS;9537 part 3 FRLS rigid P.V.C. pipes concealed in Roof Slabs with all required accessories including masonary work and labour charges etc., complete for finished item of work.	Supply and fixing of 20 mm dia 2.10 mm thickness heavy grade with IS;9537 part 3 FRLS rigid P.V.C. pipes	Supply and fixing of 20 mm dia 2.10 mm thickness heavy grade with IS;9537 part 3 FRLS rigid P.V.C. pipes	APSS No	117.30	Rmt	2933.00
62	50.000	Supply and fixing of 20 mm outer dia 2.10 mm thickness heavy grade with IS;9537 part 3 FRLS rigid P.V.C. pipes concealed in walls with all required accessories including masonary work for light, fan and separate plug points with well seasoned wooden deep box including cost and conveyance of all materials and all labour charges etc., complete	Supply and fixing of 20 mm outer dia 2.10 mm thickness heavy grade	Supply and fixing of 20 mm outer dia 2.10 mm thickness heavy grade	APSS No	129.26	Rmt	6463.00
63	22.000	Wiring with 2 runs of 14/0.3mm (1.0 Sq.mm) Fire Retardant (FR) P.V.C. insulated flexible copper cable (ISI MARK) in existing pipe with 6A switch, Ceiling rose and 3mm thick hylam sheet covering to switch control box including all labour charges etc., complete for light, bell, fan and exhaust fan points in Non Residential Buildings	Wiring with 2 runs of 14/0.3mm (1.0 Sq.mm) Fire Retardant (FR) P.V.C. insulated flexible copper cable	Wiring with 2 runs of 14/0.3mm (1.0 Sq.mm) Fire Retardant (FR) P.V.C. insulated flexible copper cable	APSS No	851.39	Point	18731.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
64	6.000	Supply and fixing of 6A 3 pin wall plug socket with 6A switch control on a common switch board with earth continuity including wire leads, earth connections along with all labour charges etc., complete.	Supply and fixing of 6A 3 pin wall plug socket with 6A switch control on a common switch board with earth continuity	Supply and fixing of 6A 3 pin wall plug socket with 6A switch control on a common switch board with earth continuity	APSS No	323.80	Nos	1943.00
65	6.000	Supply and fixing of batten holder / angle holder in lieu of ceiling rose of light point complete with all connections and all labour charges with 3.00 Watts LED Lamp (for new installation).	Supply and fixing of batten holder / angle holder in lieu of ceiling rose of light point	Supply and fixing of batten holder / angle holder in lieu of ceiling rose of light point	APSS No	256.54	Nos	1539.00
66	200.000	Supply and run of 2 of 36/0.3 mm (2.5 Sq.mm) F.R P.V.C. insulated flexible copper cable in existing pipe for mains inlcuding all labour charges etc., complete.	Supply and run of 2 of 36/0.3 mm (2.5 Sq.mm) F.R P.V.C. insulated flexible copper cable	Supply and run of 2 of 36/0.3 mm (2.5 Sq.mm) F.R P.V.C. insulated flexible copper cable	APSS No	106.75	Rmt	21350.00
67	100.000	Supply and run of 2 of 56/0.3mm (4 Sq.mm) F.R. P.V.C. insulated flexible copper cable in existing pipe for mains including all labour charges etc., complete.	Supply and run of 2 of 56/0.3mm (4 Sq.mm) F.R. P.V.C. insulated flexible copper cable	Supply and run of 2 of 56/0.3mm (4 Sq.mm) F.R. P.V.C. insulated flexible copper cable	APSS No	162.04	Rmt	16204.00
68	1.000	Supply and fixing SPN Distribution board with IP-20 protection suitable for 40 A DP Isolator (DP) Isolator as incomer and 6-32 Amp 10kA SP MCBs - 4 Nos. as out goings including internal connections and labour charges for surface / flush mounting etc., complete	Supply and fixing SPN Distribution board with IP-20 protection suitable	Supply and fixing SPN Distribution board with IP-20 protection suitable	APSS No	4743.43	Nos	4743.00
69	100.000	Supply and Run of 2 of 6 Sq.mm WPSC Aluminium cable along with No.10 SWG G.I bearer wire through PVC cleats with all accessories including labour charges etc., complete for service mains.	Supply and Run of 2 of 6 Sq.mm WPSC Aluminium cable along with No.10 SWG G.I bearer wire	Supply and Run of 2 of 6 Sq.mm WPSC Aluminium cable along with No.10 SWG G.I bearer wire	APSS No	445.64	Rmt	44564.00
70	14.000	Supply, transportation and fixing of 40 Watts tube light luminaire on wall / Ceiling with Teak Wood round blocks with all accessories including giving connections, all labour charges etc., complete with copper choke, starter etc., complete	Supply, transportation and fixing of 40 Watts tube light luminaire on wall / Ceiling with	Supply, transportation and fixing of 40 Watts tube light luminaire on wall / Ceiling with	APSS No	539.67	Nos	7555.00

Sl. No.	Estimate Quantity (only Figures)	Item Detailed Specification Description	Work Type eg. Earth Work, Electrical works.. Etc (upto 200 Characters)	Item Short Description (upto 100 Characters)	APSS/ Morth Cl. Number (upto 200 Characters)	Rate (INR) (Upto 2 Decimals)	UOM (upto 50 Characters)	Amount (INR) (Upto 2 Decimals)
71	8.000	Cost, supply and fixing of 1200 mm (48") sweep 230 V, A.C 50 Hz.Ceiling fan with 3 Blades and double ball bearings including fixing of electronic regulator and giving connections, all labour charges for fixing with all standard accessories	Cost, supply and fixing of 1200 mm (48") sweep 230 V, A.C 50 Hz.Ceiling fan	Cost, supply and fixing of 1200 mm (48") sweep 230 V, A.C 50 Hz.Ceiling fan	APSS No	2732.44	Nos	21860.00
72	8.000	Labour charges for Fixing of Ceiling fan and regulator including transportation and giving connections with twin core wire etc., complete.	Labour charges for Fixing of Ceiling fan and regulator	Labour charges for Fixing of Ceiling fan and regulator	APSS No	266.87	Nos	2135.00
73	8.000	Supply and erecting stepped type electronic for ceiling fans 900/1200/1400mm sweep complete erected on existing board.	Supply and erecting stepped type electronic for ceiling fans	Supply and erecting stepped type electronic for ceiling fans	APSS No	478.32	Nos	3827.00
								3212152.00