SCHEDULE - "A"

Schedule of Rates and Approximate Quantities

D.R 55 /2026-27, Dt:20.08.2026 **Tender Notice No.165/2026-27, Dated:09.10.2026**

Estimate Amount Rs. 13,13,000/-

Name of the Work :- **Improvements to Existing Pushkar Ghat in between K.M.29.800 to K.M.30.000 on Vasista Left Bank in Gopalapuram (Gullarevu) Village Limits of Ravulapalem Mandal in Dr.B.R.Ambedkar Konaseema District**

A The quantities here given are those upon which the lumpsum tender cost of the work is based, but they are subject to alterations omissions deductions or additions as provided for the in the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rate noted below are those governing payment of extras or deductions for omissions according to the conditions of the contract, as set forth preliminary specifications of the A.P.S.S and other conditions or specifications of this contract.

B It is to be expressly understood that the measured work is to be taken net (not withstanding any custom or practice to the contrary) according to the actual quantities when in place and finished according to the drawing or as may be ordered from time to time by the Executive Engineer and the cost calculated by measurement or weight, at the respective prices, without any additional charge for any necessary or contingent works connected therewith. The rates quoted are for works in situ and complete in every respect.

C Additions and alterations in the schedule of quantities will disqualify the tender

D In case of discrepancies between the written description of the item in the schedule-A and the detailed description in the specification of the same item, the latter shall be adopted.

Sl. No.	Probable Quantity	Description of Work	Specifica-tion	Unit in words/ Figures	Estimate Rate		Amount
					Figures	Words	
01	**02**	**03**	**04**	**05**	**06**	**07**	**08**
01	**288.00** Sqmt.	Clearing thick jungle growth (less than 50 percent open space) including bushes upto 30 cm / parthenium and other weeds including burning or disposing off the same as directed etc., complete as directed by the Engineer-in-Charge.	As directed by the Engineer-in-Charge (IRR-PMW 1-2)	1 Sqmt. (One Squere Meter)	**4.39**	Rupees Four and Paise Thirty Nine Only	**1264**
02	**544.00** Cum	Excavation in all kinds of soil including boulders upto 0.30 m dia. for foundations of canal cross drainage and other appurtenant structures and placing the excavated stuff neatly in specified dump area or disposing off the same as directed etc., complete with initial lead upto 50 m and initial lift upto 3 M as directed by the Engineer-in-Charge.	As directed by the Engineer-in-Charge (IRR-CCDW-1-1)	1 CUM (One Cubic Meter)	**489.70**	Rupees Four Hundred Eighty Nine and Paise Seventy Only	**266397**

Contractor

Executive Engineer
Godavari Head Works Division
Dowlaiswaram

01	02	03	04	05	06	07	08
03	**33.00** Cum	Excavation and removal of silt or silt mixed with sand in slussy condition from canal bed including disposing off the same in spoil bank or on the canal embankment in layers as directed etc., complete with initial lead upto 50 m and all lifts as director by the Engineer-in-Charge	As directed by the Engineer-in-Chief (PMW 3-21)	1 CUM (One Cubic Meter)	**386.30**	Rupees Three Hundred Eighty Six and Paise Thirty Only	**12748**
04	**968.00** Rmt.	Supply of Casurina Piles of size 100 to 150 mm dia of 5.50 Mts long including cost and conveyance to all materials ot site of work etc., complete as directed by the Engineer-in -charge	As directed by the Engineer-in-Charge (CE GDS Minutes of Meeting 20.08.26)	1 Rmt. (One Running Meter)	**109.00**	Rupees One Hundred Nine Only	**105512**
05	**242.00** Nos.	Fixing Casurina Posts and Bamboos in position to form a Pilebox, Closing, Removing Knots, Sharpening One Edge for Driving the Pile Driving the Post Vertically in Position, Fixing Casurina Bamboos Horizontally to Vertical Posts including cost of Bending Wire and Labour Charges and Hire Charges for equipment including cost and conveyance of all materials etc,, complete as directed by the Engineer-in-Charge	As directed by the Engineer-in-Charge (CE GDS Minutes of Meeting 20.08.26)	1 No. (One Number)	**70.00**	Rupees Seventy Only	**16940**
06	**1920.00** Rmt.	Supply and Fixing of Bamboos of size 50 to 75 mm dia of Horizontal to Piles and Labour Charges for Tying with Binding Wire and Nails at 0.30 M c/c for out side in position etc., complete as directed by the Engineer-in-Charge	As directed by the Engineer-in-Charge (CE GDS Minutes of Meeting 20.08.26)	1 Rmt. (One Running Meter)	**50.00**	Rupees Fifty Only	**96000**
07	**360.00** Sqmt.	Supply and Fixing of Bamboo Mat (Thatties) of Made with 1/4" thick 1/2 spilt 4" C/c Bamboos and Fixing them to Casurina Posts and Casurina Breasings to retain the Sand Bags, including cost and conveyance of Bamboo Thatties, Nails and Binding Wire, Labour Charges, including cost and conveyance of all Materials to site of work etc., complete for finished item of work as directed by the Engineer-in-Chief	As directed by the Engineer-in-Charge (CE GDS Minutes of Meeting 20.08.26)	1 Sqmt. (One Squere Meter)	**578.00**	Rupees Five Hundred Seventy Eight Only	**208080**

Contractor

Executive Engineer
Godavari Head Works Division
Dowlaiswaram

01	02	03	04	05	06	07	08
08	**5296.61** Nos.	Supply of Sand Filled Bags including Cost and Conveyance of all Materials, empty Cement Bangs, Sand, Labour Charges for Filling, Stiching with Country Twine and conveyance and placing of the Bag in position including contractors profit 13.615% and overhead charges etc., complete as directed by the Engineer-in-Charge	As directed by the Engineer-in-Charge	1 No. (One Number)	**28.60**	Rupees Twenty Eight and Paise Sixty Only	**151483**
09	**1000.00** Sqmt.	Providing and laying NWG 700 Needle Punched Coir Geocomposite Mat made of 100% coconut fibre reinforced with polyester geogrid having an minimum mass of 700 g/m2, Minimum thickness of 7.3 MM, Minimum tensile strength of 8.5 kN/m, minimum cbr Puncture resistance of 1600 N, and water premeability of 95 MM/Sec., Complete as per the manufacturer's specificaions and as directed by the Engineer-in-charge	As directed by the Engineer-In-Charge. (Rate as per Quotation)	1 Sqmt. (One Squere Meter)	**190.00**	Rupees One Hundred Ninety Only	**190000**
10	**5.00** Sqm	Flooring with Chequrred terrazoTiles of 22mm thick (Medium shade),1st.quality as approved by the Engineer - in - charge set over a base coat of CM (1:6), 12mm thick laid over flooring bed / V.R.C.C. slab, with neat cement slurry of honey like consistency spread at the rate of 3.3 Kgs of cement per Sq.m and jointed with neat white cement paste to full depth mixed with pigment of matching shade including cost and conveyance of all materials like cement, sand, water,tiles etc. to site, seigniorage charges, sales and other taxes on all materials, all operational, incidental and labour charges such as mixing of cement mortar, laying, curing, lift charges etc., complete for finished item of work.(APSS No.701 & 707) for Bathing ghat steps. as director by the Engineer-in-Charge	As directed by the Engineer-in-Chief (BLD CSTN 9-4 (102)	1 Sqmt. (One Squere Meter)	**941.20**	Rupees Nine Hundred Forty One and Paise Twenty Only	**4706**
11	**15.00** Rmt.	Supply and fixing 100 mm dia G.I. Pipes B Class for vertical posts on platforms including cost and conveyance and labour charges for fixing etc., complete as director by the Engineer-in-Charge	As directed by the Engineer-in-Chief (S.No.32 of P.13 & BSoR P.252 BMW F-78	1 Rmt. (One Running Meter)	**899.80**	Rupees Eight Hundred Ninety Nine and Paise Eighty Only	**13497**

Contractor

Executive Engineer
Godavari Head Works Division
Dowlaiswaram

01	02	03	04	05	06	07	08
12	**15.00** Sqmt.	Supply and fixing of Hot dipped Galvanised Iron chain link mesh 8 gauge (4mm) 63 MMX63MM gauge including cost conveyance of all materials to site of work and labour charges for fixing to G.I. Pipes etc., complete as director by the Engineer-in-Charge.	As directed by the Engineer-in-Chief (S.No.162 of P.27 BSoR)	1 Sqmt. (One Squere Meter)	**662.40**	Rupees Six Hundred Sixty Two and Paise Forty Only	**9936**
13	**61.20** Sqmt.	White washing two coats with whiting of approved quality to give an even shade after thoroughly brushing the surface to remove all dirt and remaining to loose powdered materials including cost of all materials, labour charges and incidental such as scaffolding, lift charges etc., complete for finished item of work but excluding conveyance charges of materials as directed by the Engineer-in-charge	As directed by the Engineer-In-Charge. (BLD-CSTN-11-5)(BMS-W-68)	1 Sqmt. (One Squere Meter)	**55.80**	Rupees Fifty Five and Paise Eighty Only	**3415**
						PART - I Total:-	**1079978**
		PART – II (L.S.PROVISIONS):					
01	Provision towards Seigniorage Charges (SC+DMF+Merit)		0	0	0	Rs.	**0**
02	Provision towards NAC @ 0.10% (Part1+SC)		1079978	0	**1079978**	Rs.	**1080**
03	Provision towards GST Charges @ 18.00% (Part1+SC+NAC)		1079978	1080	**1081058**	Rs.	**194590**
						PART - II Total:-	**195670**
						Grand Total (PART - I + II)	**1275648**
Rupees Twelve Lakhs Seventy Five Thousand Six Hundred Forty Eight Only							

Contractor

Executive Engineer
Godavari Head Works Division
Dowlaiswaram